



NARRATIVE:

The purpose of this survey was to establish the boundaries of Block G in South Pendleton and Reservation Addition to the City of Pendleton.
 City of Pendleton monuments are at the intersections of South Main Street + Emigrant and South Main + Isaac Streets; a Pk nail at SE Second and Emigrant, set by Krumben Engineering Co., County Survey Drwg No. 0-62-A; and a pin at the Southwest corner of the Montgomery Ward's property set by Stanley G. Wallis in 1964, County Survey Drwg No 6-337-A; were tied together and found to have the correct relationships as shown on the original plots. They were used to set the 3/8" x 30" iron rebar with aluminum caps.
 Bearings are based upon the City of Pendleton drawing of "Reservation Addition Monuments Found" and are Pendleton Local Grid.
 The City of Pendleton would request that any new sewer lines to be tapped into the line on SE First Street.

- denotes water line
- - - denotes gas line
- - - denotes power line
- - - denotes television line
- denotes 1/2" iron rebar
- denotes manhole
- denotes fire hydrant
- denotes power poles
- - - denotes telephone line
- denotes valve
- denotes water meter
- denotes telephone manhole
- denotes telephone boxes
- denotes storm sewer
- denotes sanitary sewer
- denotes cleanout
- denotes catch basin
- denotes 3/8" x 30" iron pin with aluminum cap stamped P.L.S. 933 set
- denotes Pk nail

KRUMBEIN ENGINEERING LTD. ENGINEERS - SURVEYORS - PLANNERS 361 S.E. Second Pendleton, Oregon	Scale 1" = 20'	Drn. By MLD	Drwg. No. 83-210	Revision 1
	Date 8-10-83	Chk. By DHK	Plot No. 83-83	Revision 2
Boundary Survey for SALVATION ARMY CHURCH		REGISTERED PROFESSIONAL LAND SURVEYOR <i>David H. Krumbein</i> GREGG DAVID H. KRUMBEIN 933	RECEIVED BY Umatilla County Surveyor Date 9-2-83 Rec'd By <i>bc</i> No. 83-164-C	
Section 11, T2N, R32E, W.M.				