

J-AD

GPS CONTROL STATION

OREGON STATE PLANE, NORTH ZONE

STATION NAME: 68	GEODETIC COOR: NAD 83(91):
SECTION: SE 1/4, S12, T.2N., R.31E., UMATILLA COUNTY, OREGON	LAT: 45° 39' 36.09269" N LONG: 118° 52' 19.97849" W
DATE SET: EXISTING MONUMENT	STATE PLANE CO-ORDINATES, NAD 83-91, INT.FT.:
SURVEYOR: WILLIAM R. WELLS PLS 1106	N: 730927.082 E: 8618261.924 THETA: 1° 09' 15.85"
FIRM: WILLIAM R. WELLS, LAND SURVEYING AND PLANNING P.O. BOX 1696 PENDLETON, OR 97801 (541) 276-6362	SCALE FACTOR: 0.99993133 ELEV: 999.27 US.FT. ELEV. DATUM: LOCAL, CITY OF PENDLETON
ORDER: SECOND ORDER, CLASS I	CITY OF PENDLETON CO-ORDINATES INT.FT.:
	N: 47026.256 E: 25916.878

LOCATION:

STATION IS LOCATED IN THE CITY OF RIETH. FROM INTERSECTION OF OLD PENDLETON RIVER ROAD AND BIRCH CREEK ROAD FOLLOW BIRCH CREEK ROAD SOUTHWESTERLY AS THE ROAD CURVES TO THE WEST. STATION IS LOCATED 2 FEET M/L WEST AND 6 FEET M/L SOUTH OF WEST END OF GUARDRAIL ALONG CURVE.

STATION IS A 1 1/2" ALUMINUM CAP ON A 5/8" PIN MARKED "CITY OF PENDLETON, RIETH". A SURVEY MONUMENT SIGN ON A STEEL FENCE POST IS 1 FOOT SOUTH OF STATION.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Renews 6-30-96