

GPS CONTROL STATION

OREGON STATE PLANE, NORTH ZONE

STATION NAME: 77	GEODETIC COOR: NAD 83(91):
SECTION: SE 1/4, S9 OR SW 1/4, S10, T.2N., R.32E., UMATILLA COUNTY, OREGON	LAT: 45° 39' 50.57667" N LONG: 118° 48' 27.60252" W
DATE SET: EXISTING MONUMENT	STATE PLANE CO-ORDINATES, NAD 83-91, INT.FT.:
SURVEYOR: WILLIAM R. WELLS PLS 1106	N: 732732.848 E: 8634731.515 THETA: 1° 12' 00.64" SCALE FACTOR: 0.99993193 ELEV: 1053.09 US.FT. ELEV. DATUM: LOCAL, CITY OF PENDLETON
FIRM: WILLIAM R. WELLS, LAND SURVEYING AND PLANNING P.O. BOX 1696 PENDLETON, OR 97801 (541) 276-6362	CITY OF PENDLETON CO-ORDINATES INT.FT.:
ORDER: SECOND ORDER, CLASS I	N: 48480.402 E: 42423.196

LOCATION:

STATION IS LOCATED IN GRASSY AREA ENCLOSED BY I-84 WESTBOUND EXIT #209. STATION IS SOUTH 28° WEST, 50 FEET M/L OF LONE SCOTCH PINE.

STATION IS A 2 1/2" BRASS CAP IN A CONCRETE PAD MARKED "STATE HIGHWAY DEPARTMENT REFERENCE, RB2".

STATION IS RESERVATION BOUNDARY MONUMENT NO. 2.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Renews 6-30-96