

HORIZONTAL CONTROL DATA

OREGON STATE PLANE, NORTH ZONE (3601)

STA. NAME: 9334

QUARTER SECTION: SW

GEODETIC COOR: NAD 83(91)

SEC. 24 TWP.4 N,RGE.28E  
UMATILLA CO.ORE.

LAT: 45°48'28.75020" N

DATE SET: JULY ,1993

LONG: 119°16'17.27918" W

SURVEYOR: WALTER L. CASWELL  
PLS 737

SP. COOR: NAD 83(91)

FIRM: EAGLE GPS SURVEY CORP  
13545 NW SCIENCE PARK DR  
PORTLAND, OR. 97229  
(503) 643-1073

N: 783067.559 INT.FT.

E: 8515377.666 INT.FT.

THETA: 0°52'16.531"

TYPE: GPS

SCALE FACTOR: 0.999956850

ORDER: SECOND, CLASS: 1

ELEV: 640.150 US.FT.

ELEV. DATUM: NGVD 29

\*\*\*\*\*  
DIRECTIONS "TO REACH"

FROM THE INTERSECTION OF FEEDVILLE ROAD AND HWY. 395, GO WEST ON FEEDVILLE ROAD 1.25 MILE, THEN GO NORTH 700 FEET CROSS COUNTRY TO MONUMENT. CAN ALSO ACCESS FROM CROP PATH AT 24 MILE POST ON FEEDVILLE ROAD. TRAVEL NORTHERLY ON CROP PATH 0.1 MILE TO MONUMENT.

STATION IS A 5/8" X 30" IRON ROD WITH A YELLOW PLASTIC CAP INSCRIBED "BUFORD ASSOC. PLS 1148".

STATION IS 700 FEET NORTH OF FEEDVILLE ROAD BETWEEN TWO CIRCULAR CROP AREAS.

METERS X 3.28083333333 = U.S. FEET  
METERS X 3.28083989501 = INTERNATIONAL FT.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Walter Caswell*

OREGON  
JULY 8, 1966  
WALTER L. CASWELL  
737

EXP. 12/31/93