

HORIZONTAL CONTROL DATA

OREGON STATE PLANE, NORTH ZONE (3601)

STA. NAME: 9342

QUARTER SECTION: NE

GEODETIC COOR: NAD 83(91)

SEC. 28 TWP.4 N,RGE.28E
UMATILLA CO.ORE.

LAT: 45°48'06.64400" N

DATE SET: JULY ,1993

LONG: 119°19'14.34848" W

SURVEYOR: WALTER L. CASWELL
PLS 737

SP. COOR: NAD 83(91)

FIRM: EAGLE GPS SURVEY CORP
13545 NW SCIENCE PARK DR
PORTLAND, OR. 97229
(503) 643-1073

N: 780641.770 INT.FT.

E: 8502868.776 INT.FT.

THETA: 0°50'10.956"

TYPE: GPS

SCALE FACTOR: 0.999955657

ORDER: SECOND, CLASS: 1

ELEV: 584.205 US.FT.

ELEV. DATUM: NGVD 29

DIRECTIONS "TO REACH"

FROM THE INTERSECTION OF FEEDVILLE ROAD AND HWY. 207, GO SOUTH ON
HWY. 207 0.3 MILE.

STATION IS A 5/8" X 30" IRON ROD WITH A YELLOW PLASTIC CAP
INSCRIBED "BUFORD ASSOC. PLS 1148".

STATION IS 20 FEET EAST OF CENTERLINE OF HWY. 207, 90 FEET NORTH
OF CENTERLINE OF "BUD RICH POTATO" FACTORY ACCESS ROAD.

METERS X 3.28083333333 = U.S. FEET
METERS X 3.28083989501 = INTERNATIONAL FT.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Walter L. Caswell

OREGON
JULY 8, 1966
WALTER L. CASWELL
737

Exp. 12/31/93