

Bonneville Power Administration
Geodetic Control Data Sheet

Station: WM049 (249)
Project: Wallula-Smiths Harbor-McNary
Section: NE 1/4 20 Township: 5 North Range: 29 East Meridian: Willamette
County: Umatilla State: OR USGS Quad: Hat Rock, Oregon
Surveyor: M R Heidecke Date Surveyed: July, 2001

Instrument:

The horizontal coordinates and orthometric elevation were established by GPS observations using six Trimble 4000 SSI dual frequency receivers with Compact L1/L2 antennae with ground plane.

Adjustment:

The Basis of Coordinates for this survey is the Oregon State Coordinate System, North Zone, NAD 83 (1998). The horizontal component of the least squares adjustment was constrained by holding NGS Stations B 340 (A), B 502 (B), PENDLETON (B), STANFIELD EAST BASE RESET (B), and BURDEN (B). The vertical component of the least squares adjustment was constrained by holding NGS Benchmarks B 340 (First Order Class II), B 502 (First Order Class II), BURDEN (Second Order Class II), V 203 (Second Order Class 0), G 640 (First Order Class I). The elevation for point 106, 201, 249, and 255 were determined by differential leveling from G 640, D 502, E 525 and F 431 respectively and held.

Horizontal Datum: NAD83 (1998) Linear Unit: International Feet
Vertical Datum: NAVD88 Linear Unit: U.S. Survey Feet

Latitude: <u>N 45-54-10.22593</u>	Longitude: <u>W 119-12-10.99955</u>
US State Plane Coordinate System: <u>Oregon North Zone - 3601</u>	
Northing: <u>817,924.238</u>	Easting: <u>8,532,265.890</u>
Orthometric Elevation: <u>456.52</u>	Ellipsoid Height: <u>385.37</u>
Combined Factor: <u>0.99995837</u>	Convergence: <u>- 0-55-11</u>
Confidence: 95% Confidence ("1.96 Sigma") Values	
<u>Northing-0.009</u>	<u>Easting-0.007</u> <u>Elevation-0.000</u>

Monumentation: Yellow plastic cap on 5/8-inch steel rod flush with ground.
Stamping: Edwards 951

To-Reach Description:

Begin at Umatilla Post Office, Umatilla, OR. 97882. Drive east on Highway 730, 5.1 miles to station in the south right-of-way fence. Station is 54.5 feet south of the centerline of Highway #730 in the south right-of-way fence of Highway #730, and 400 feet west of MP 190.

Witness post is a yellow carsonite marker inscribed with BPA logo, bearing and distance to station.

RECEIVED BY
Umatilla County Surveyor
Date _____
Rec'd By _____
02-19-01
J