

HORIZONTAL CONTROL DATA

OREGON STATE PLANE, NORTH ZONE (3601)

STA. NAME: 9311

QUARTER SECTION: SW

GEODETIC COOR: NAD 83(91)

SEC. 22 TWP.5 N,RGE.28E
UMATILLA CO.ORE.

LAT: 45°53'37.57437" N

DATE SET: JULY ,1993

LONG: 119°18'14.12576" W

SURVEYOR: WALTER L. CASWELL
PLS 737

SP. COOR: NAD 83(91)

FIRM: EAGLE GPS SURVEY CORP
13545 NW SCIENCE PARK DR
PORTLAND, OR. 97229
(503) 643-1073

N: 814221.043 INT.FT.

E: 8506638.509 INT.FT.

THETA: 0°50'53.665"

TYPE: GPS

SCALE FACTOR: 0.999974726

ORDER: SECOND, CLASS: 1

ELEV: 467.552 US.FT.

ELEV. DATUM: NGVD 29

DIRECTIONS "TO REACH"

FROM THE INTERSECTION OF HWY. 395 (UMATILLA-STANFIELD HWY.) AND
BENSEL ROAD, GO WEST ON BENSEL ROAD 0.13 MILE TO MONUMENT ON
NORTH RIGHT OF WAY.

STATION IS A 5/8" X 30" IRON ROD WITH A YELLOW PLASTIC CAP
INSCRIBED "BUFORD ASSOC. PLS 1148".

STATION IS 33 FEET NORTH OF CENTERLINE OF BENSEL ROAD, 65 FEET
NORTH OF POWER POLE NO. 5N28E (AND TELEPHONE RISER) #271900.

METERS X 3.28083333333 = U.S. FEET
METERS X 3.28083989501 = INTERNATIONAL FT.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Walter L. Caswell

OREGON
JULY 8, 1966
WALTER L. CASWELL
737

EXP. 12/31/93