

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla. DATE: 03/20/20.

CORNER DESIGNATION: A-19, The North One-Quarter corner of Section 3, Township 1 North, Range 31 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC: Corner was originally established by Josiah A. Burnett under Contract No. 92 dated September 12, 1860. Notes state: Set post for 1/4 Sec. Cor., drove charred stake and raised mound with trench as per instructions. John Kimbrell, County Surveyor, in his January, 1909 Survey No. 274, reestablished this corner and set a 2" pipe, 3 1/2' long. Kimbrell's Survey No. 274 is found in the Record of Private Survey Books.

MONUMENT AND ACCESSORIES FOUND: Found a 2 1/2" O.D. pipe buried 18" below ground line at the projected intersection of fence lines West and South. The corner area has been farmed over.

**MONUMENT MARKING DETAIL:**

T2N R31E  
S35  
1/4 -----  
S2  
T1N  
2020  
54657PLS

MONUMENT SET: I drove a 5/8 by 15" rebar into the found pipe and capped with a purple plastic cap marked "Wells Surveying 54657PLS". The capped rebar is the measure point. Nailed a Witness sign to a railroad tie in the East-West fence, 35' West of the corner monument.

**New accessories:**

A silver Deep-1 magnet bears N 54°17' E, 30.2'.  
A 5/8 by 24" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears S 00°40' E, 30.6'.  
A 5/8 by 24" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears S 00°07' E, 50.7'.  
A 5/8 by 24" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears S 00°45' E, 73.5'.  
The rebar accessories are set in the remains of an old fence line extending South from the corner monument. Wired bearing object signs to each of the rebar accessories. Buried a bearing object sign with the Deep-1 magnet, which is buried 18" below ground line.  
Bearings to accessories are State Plane Grid bearings.

**LOCATION AND COMMENTS:**

Corner falls on the Westerly side of a farmed field, in the field corner.

**OREGON STATE PLANE COORDINATE, North Zone NAD 83(91), International Feet Units:**

N: 709819.10  
E: 8611016.10

FIRM: Wells Surveying  
P.O. Box 1696  
Pendleton, OR 97801

Surveyor's Seal

\1N31A-19



RENEWS: 6:30:20

20-043-C