

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla. DATE: 03/12/20.

CORNER DESIGNATION: A-3, The North One-Quarter corner of Section 6, Township 1 North, Range 31 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC: Corner was originally established by Josiah A. Burnett under Contract No. 92 dated September 12, 1860. Notes state: Set post for 1/4 Sec. Cor., drove charred stake and raised mound with trench as per instructions.

MONUMENT AND ACCESSORIES FOUND: Found a 14 by 10 by 6" set, rough basalt stone at ground level on the West side of a rock jack at angle point in East-West fence line. Stone is marked "1/4" on South face. There are a few stone mounds from previous fencing extending North from corner stone. I find no record for the establishment of this stone. The stone is 1 1/2' South of an East-West fence.

MONUMENT MARKING DETAIL:

T2N R31E
S31
1/4 -----
S6
T1N
2020
54657PLS

MONUMENT SET: At the position of the found stone, set a 2 1/2" brass cap in 1 1/4 by 30 galvanized iron pipe 22" in the ground and surrounded with a 2 1/2' stone collar. Placed corner stone on the North side of brass cap monument. Brass cap is marked as shown in Monument Marking Detail. Nailed a Witness sign to wood post in fence jack 4' East of corner.

New accessories:

A 5/8 by 18" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears N 88°20' E, 35.1', in fence line.

A 5/8 by 18" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears S 38°26' E, 23.8', by fence gate post.

A 5/8 by 18" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears S 41°48' W, 33.9'.

A 5/8 by 18" rebar with blue plastic cap marked "ells Surveying 54657PLS" bears N 82°06' W, 23.8', in fence line.

Attached bearing object signs to the rebar accessories.

Bearings to corner accessories are State Plane Grid bearings.

LOCATION AND COMMENTS: Corner falls just 1 1/2' South of an East-West fence line at an angle point in the fence line. There is a farm road about 10' South of the corner.

OREGON STATE PLANE COORDINATE, North Zone NAD 83(91), International Feet Units:

N: 709613.56

E: 8589987.22

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

Surveyor's Seal

\IN31A-3

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Jason M. Wells
OREGON
NOVEMBER 29, 2010
JASON M. WELLS
54657PLS

RENEWS: 6:30:20

20-043-C