

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla. DATE: 03/12/20.

CORNER DESIGNATION: A-5, The Northeast corner of Section 6, Township 1 North, Range 31 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC: Corner was originally established by Josiah A. Burnett under Contract No. 92 dated September 12, 1860. Notes state: Set post for corner to Secs. 5, 6, 31 and 32, drove charred stake and raised mound with trench as per instructions.

MONUMENT AND ACCESSORIES FOUND: Found a 10 by 4 by 4" above ground line solidly set stone marked with "X" on top and 5 grooves on East face. I find no record for the establishment of this stone. The stone is 3' South of an East-West fence line with berm evidence of an old fence extending North. There is another stone set vertically Southeast of the marked stone.

MONUMENT MARKING DETAIL:

T2N R31E
S31|S32

S6|S5
T1N
2020
54657PLS

MONUMENT SET: This is a beautiful and solidly set marked stone. I leave the stone in place for future generations to view and drill a hole at the "X" on top of the stone and set a 1 1/2" aluminum washer stamped "Wells Surveying 54657PLS", secured to a 2" Magspike set with lead in the drilled hole. There is another stone, set vertically, about 10" East of the corner stone. Nailed Witness sign to railroad tie in fence line, North of the corner.

New accessories:

A 5/8 by 30" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears N 85°09' E, 20.4', in fence line.

A 5/8 by 24" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears S 43°22' E, 38.3'.

A 5/8 by 18" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears S 30°22' W, 39.8'.

A 5/8 by 24" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears N 79°54' W, 19.8'.

Attached bearing object signs to the rebar accessories.

Bearings to corner accessories are State Plane Grid bearings.

LOCATION AND COMMENTS: Corner falls just South of an East-West fence line. The corner area is steep.

OREGON STATE PLANE COORDINATE, North Zone NAD 83(91), International Feet Units:

N: 709606.19

E: 8592609.21

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

Surveyor's Seal

\IN31A-5



RENEWS: 6:30:20

20-043-C