

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla. DATE: 03/19/20.

CORNER DESIGNATION: A-9, The Northeast corner of Section 5, Township 1 North, Range 31 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC: Corner was originally established by Josiah A. Burnett under Contract No. 92 dated September 12, 1860. Notes state: Set post for corner to Secs. 4, 5, 32 and 33, drove charred stake and raised mound with trench as per instructions. This corner was recovered by County Surveyor Willard Bradley in his Survey No. 411, dated April, 1916. Bradley recovered "Old Cor. Stone and Mound".

MONUMENT AND ACCESSORIES FOUND: Found a 4 by 6 by 10" above ground line solidly set stone marked with "X" on top. This stone is assumed to have been set by Bradley. There are a couple other stones beside the marked stone. The marked stone is about 2' West of a railroad tie fence corner post with fences extending North and S 60° W.

MONUMENT MARKING DETAIL:

T2N R31E
S32|S33

· S5|S4
T1N
2020
54657PLS

MONUMENT SET: Moved the corner stone aside Easterly and in it's place set a 5/8 by 24" rebar 22" in the ground. The rebar is capped with a 2" aluminum cap marked as shown in the Monument Marking Detail. Nailed a Witness sign to railroad tie fence corner post East of the corner.

New accessories:

A 5/8 by 15" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears N 28°11' E, 29.3'.
A 5/8 by 15" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears S 65°23' E, 26.1'.
A 5/8 by 15" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears S 24°53' W, 28.7'.
A 5/8 by 15" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears N 63°55' W, 30.8'.
Attached bearing object signs to the rebar accessories.
Bearings to corner accessories are State Plane Grid bearings.

LOCATION AND COMMENTS: Corner falls about 100' North of a drainage in near a fence corner.

OREGON STATE PLANE COORDINATE, North Zone NAD 83(91), International Feet Units:

N: 709594.07
E: 8597856.03

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

Surveyor's Seal

\1N31A-9



RENEWS: 6:30:20

20-043-C