

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla. DATE: 03/27/20.

CORNER DESIGNATION: C-9, The East One-Quarter corner of Section 5, Township 1 North, Range 31 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC: Corner was originally established by Josiah A. Burnett under Contract No. 92 dated September 12, 1860. Notes state: Set a post for 1/4 Sec. Cor., drove charred stake and raised mound with trench as per instructions. Willard Bradley, County Surveyor, reestablished this corner in his April, 1916 Survey No. 411, and set a stone of unknown dimensions. Survey No. 411 record can be found in the Record of Private Survey Books.

MONUMENT AND ACCESSORIES FOUND: Found and accepted a solidly set 14 by 6 by 8" above ground stone set under a East-West fence line, marked "1/4" on West face. I assume this is the Bradley stone, but Bradley's Survey does not report stone dimensions.

MONUMENT MARKING DETAIL:

T1N R31E
1/4
S5|S4
2020
54657PLS

MONUMENT SET: For the corner monument, I drill a hole in the top of the found marked stone and set a 1 1/2" aluminum disk marked "Wells Surveying 54657PLS" secured to a 2" Magspike set with lead in the drilled hole. Nailed a Witness sign to wood post in existing fence East of the corner.

New accessories:

A 5/8 by 15" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears N 89°21' E, 37.8'.
A 5/8 by 15" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears N 89°05' E, 17.9'.
A 5/8 by 24" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears N 87°35' W, 17.0'.
A 5/8 by 15" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears N 89°01' W, 35.7'.
Rebars are set in the existing East-West fence. Wired bearing object signs to the rebar accessories.
Bearings to accessories are State Plane Grid bearings.

LOCATION AND COMMENTS: Corner is located on a North facing hillside in an East-West fence line.

OREGON STATE PLANE COORDINATE, North Zone NAD 83(91), International Feet Units:

N: 706769.96
E: 8597945.85

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

Surveyor's Seal

\1N31C-9



RENEWS: 6:30:20

20-043-C