

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla. DATE: 03/12/20.

CORNER DESIGNATION: E-1, The Southwest corner of Section 6, Township 1 North, Range 31 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC: Corner was originally established by David P. Thompson under Contract No. 81 dated July 8, 1859. Notes state: Set post for corner to Secs. 6, 7, 1 & 12, and build mound of earth with pits, trench and etc., as per instructions. In Survey No. Q-51-C, in 1956, John Gray, Engineer, determined a position for this corner during his Survey for a communication tower. Grays map does not reveal a monument for this corner. In Survey No. 05-52-B, in 2005, Robert Stratton computed a position for this corner but did not recover a corner monument, during his survey for ADCOMM. Stratton's computed position is based on the Gray's Survey No. Q-51-C position.

MONUMENT AND ACCESSORIES FOUND: None. Reestablished corner position by reference to Stratton Survey No. 05-52-B. The corner area is currently in an active CRP field, and the fence lines around the corner point a crooked and irregular and don't represent good possessory lines. See Sheet 2 of 2 of the present survey for reestablishment detail.

**MONUMENT MARKING DETAIL:**

T1N  
R30 E | R31E  
· S1|S6  
-----  
S12|S7  
2020\_  
54657PLS

MONUMENT SET: Set a 5/8 by 18" pointed rebar 18" in the ground in a hole drilled into rock. Rebar is capped with a 2" aluminum cap marked as shown in Monument Marking Detail. The soil at the corner point is very shallow.

**New accessories:**

A 5/8 by 18" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears N 28°04' E, 22.3', at old fence corner.

A 5/8 by 15" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears S 85°16' E, 76.1'.

A 5/8 by 15" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears S 25°10' E, 69.0', at old gate post with old fence line South.

A 5/8 by 15" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears S 75°49' W, 54.1', at a newer wire fence line angle point.

Wired bearing object signs to the rebar accessories. Nailed a Witness sign to a wood fence post at the Northeast accessory rebar.

Bearings to corner accessories are State Plane Grid bearings.

LOCATION AND COMMENTS: Corner falls in a active field between crooked fence lines.

OREGON STATE PLANE COORDINATE, North Zone NAD 83(91), International Feet Units:

N: 704290.50

E: 8586822.73

FIRM: Wells Surveying  
P.O. Box 1696  
Pendleton, OR 97801

Surveyor's Seal

\1N31E-1

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Jason M. Wells*  
OREGON  
NOVEMBER 29, 2010  
JASON M. WELLS  
54657PLS

RENEWS: 6!30!20

20-043-C