

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla. DATE: 03/27/20.

CORNER DESIGNATION: E-3, The South One-Quarter Section corner of Section 6, Township 1 North, Range 31 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC: Corner was originally established by Josiah A. Burnett under Contract No. 92 dated September 12, 1860. Notes state: Set a post for 1/4 Sec. Cor., drove charred stake and raised mound with trench as per instructions. This corner was recovered by Willard Bradley, County Surveyor, in his Survey No. 411, dated April, 1916. Bradley's notes state "Gov. 1/4 cor. Old stake and stone". Record for Survey No. 411 is found in the Record of Private Survey Books.

MONUMENT AND ACCESSORIES FOUND: None. The corner area has been farmed and is currently in a CRP field.

MONUMENT MARKING DETAIL:

T1N R31E
S6
1/4 -----
S7
. 2020
54657PLS

MONUMENT SET: I reestablish this corner point by extending the bearing and distance between the Northeast corner of Section 7 and the fence corner found at the East 1 1/6 th corner on the North line of Section 7, Westerly, the same bearing and distance. At the reestablished corner point in the CRP field, set a 2 1/2" brass cap on 1 1/4 by 30" galvanized iron pipe 22" in the ground to refusal. The soil around the corner point is shallow. The brass cap is marked as shown in the Monument Marking Detail and the corner monument is surrounded with a 2 1/2' diameter mound of earth and stone. Set a steel fence post 2' North of corner and attached Witness sign.

New accessories:

A silver Deep-1 magnet bears N 39°19' E, 25.5'.

A 5/8 by 15" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears S 13°35' E, 52.6', set in North bank of farm road.

A 5/8 by 15" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears S 48°53' W, 36.8', set in North bank of farm road.

A orange Deep-1 magnet bears N 30°50' W, 21.7'.

Wired bearing object signs to the rebar accessories. Buried bearing object signs with the Deep-1 magnets which are set 18" below ground line.

Bearings to accessories are State Plane Grid bearings.

LOCATION AND COMMENTS: Corner is located in a previously farmed field which is currently a CRP field. There are no nearby possessory features. The corner is about 40' North of and old farm road.

OREGON STATE PLANE COORDINATE, North Zone NAD 83(91), International Feet Units:

N: 704267.36

E: 8590173.63

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

Surveyor's Seal

\1N31E-3



RENEWS: 6:30:20

20-043-C