

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla. DATE: 04/03/20

CORNER DESIGNATION: G-17, The East One-Quarter corner of Section 10, Township 1 North, Range 31 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC: Corner was originally established by Josiah A. Burnett under Contract No. 92 dated September 12, 1860. Notes state: Set post for 1/4 Sec. Cor., drove charred stake and raised mound with trench as per instructions. John Kimbrell, in Survey No. 274, in January, 1909 recovered this corner but does not state what was found. Record for Survey No. 274 is found in the Record of Private Surveys Book.

MONUMENT AND ACCESSORIES FOUND: Found and accepted a 5' diameter stone mound North of the toe of a steep South facing hillside. There are no nearby possessory features.

MONUMENT MARKING DETAIL:

T1N R31E
1/4
S10|S11
2020
54657PLS

MONUMENT SET: At the center of the stone mound, set a 5/8 by 24" rebar in hole drilled in rock and capped with a 2" aluminum cap marked as shown in Monument Marking Detail. The rebar monument is surrounded with a mound of stone. Wired a Witness sign to a rock placed on top of the stone mound.

New accessories:

A 5/8 by 15" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears N 31°13' E, 23.7'.
A 5/8 by 15" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears S 48°26' E, 22.9'.
A 5/8 by 15" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears S 45°35' W, 21.3'.
A 5/8 by 15" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears N 46°31' W, 29.5'.
Wired bearing object signs to the rebar accessories.
Bearings to accessories are State Plane Grid bearings.

LOCATION AND COMMENTS: Corner falls about 100' North of Coombs Canyon road just North of the foot of a steep South facing slope. Corner is visible from road.

OREGON STATE PLANE COORDINATE, North Zone NAD 83(91), International Feet Units:
N: 701783.35
E: 8608566.22

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

Surveyor's Seal

\1N31G-17



RENEWS: 6/30/20

20-043-C