

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla. DATE: 04/03/20

CORNER DESIGNATION: G-9, The East One-Quarter corner of Section 8, Township 1 North, Range 31 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC: Corner was originally established by Josiah A. Burnett under Contract No. 92 dated September 12, 1860. Notes state: Set post for 1/4 Sec. Cor., drove charred stake and raised mound with trench as per instructions. Willard Bradley, in Survey No. 411 in April 1916, surveyed through this corner but did not recover or remonument it. Record for Survey No. 411 is found in the Record of Private Surveys Book.

MONUMENT AND ACCESSORIES FOUND: Found and accepted 26 by 14 by 12" set stone in 3 1/2' stone mound. Corner stone is marked "1/4" on West face. The "4" is a closed 4, the only closed 4 found on marked 1/4 stones in the entire North half of T1N., R31E., W.M. I find no record for the recovery or establishment of this corner. I also recovered a set, 10 by 6 by 15" out of ground stone, marked "X" on top, at the North 1 1/6 th corner common to Sections 8 and 9. There is no record for this 1 1/6 th stone. It was found by chance when navigating to the Northeast corner of Section 8. It is in a saddle of a South Facing hillside with no possessory features nearby. See the Survey Map for additional information.

MONUMENT MARKING DETAIL:

T1N R31E
1/4
S8|S9
2020
54657PLS

MONUMENT SET: I remove the corner stone and in it's place set a 5/8 by 24" rebar in hole drilled in rock and capped with a 2" aluminum cap marked as shown in Monument Marking Detail. The rebar monument is surrounded with a mound of stone. Placed the corner stone, marks down, South of the rebar monument. Wired a Witness sign to a rock in the stone mound.

New accessories:

A 5/8 by 15" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears N 30°29' E, 28.6'.
A 5/8 by 15" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears S 51°47' E, 35.5'.
A 5/8 by 15" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears S 08°18' W, 29.0'.
A 5/8 by 15" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears N 19°34' W, 22.5'.
Wired bearing object signs to the rebar accessories.
Bearings to accessories are State Plane Grid bearings.

LOCATION AND COMMENTS: Corner falls on the West side of a rounded ridge facing South. The corner area is very rocky. See notes above regarding the 1/16 th corner found North of this corner.

OREGON STATE PLANE COORDINATE, North Zone NAD 83(91), International Feet Units:

N: 701492.75
E: 8598062.18

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

Surveyor's Seal

\IN31G-9



RENEWS: 6/30/20

20-043-C