

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla. DATE:

CORNER DESIGNATION: J-11, The North One-Quarter corner of Section 16, Township 1 North, Range 31 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC: Corner was originally established by Josiah A. Burnett under Contract No. 92 dated September 12, 1860. Notes state: Set a post for 1/4 sec. cor., drove charred stake and raised mound with trench as per instructions.

MONUMENT AND ACCESSORIES FOUND: None. I reestablished this corner on the parallel of latitude between the Northeast and Northwest corners of Section 16 holding the Southerly projection of a fence line that begins at the North 1/4 corner of Section 9 and runs South to a point just North of Coombs Canyon Road.

**MONUMENT MARKING DETAIL:**

T1N R31E  
S9  
1/4 -----  
S16  
2020  
54657PLS

MONUMENT SET: At the reestablished corner point. Set a 2 1/2" brass cap on 1 1/4 by 30" galvanized iron pipe 26" in the ground. Cap is marked as shown in the Monument Marking Detail. Set a steel fence post with Witness sign attached 2' South of the corner monument.

**New accessories:**

- A silver Deep-1 magnet bears N 21°54' E, 30.6'.
  - A purple Deep-1 magnet bears S 71°03' E, 33.5'.
  - A blue Deep-1 magnet bears S 25°01' W, 30.2'.
  - A orange Deep-1 magnet bears N 71°15' W, 30.2'.
- Placed a bearing object sign below ground by each Deep-1 magnet. Deep-1 magnets are buried 18" below ground line.  
Bearings to accessories are State Plane Grid bearings.


LOCATION AND COMMENTS: Corner is located in a CRP field about 900' South of Coombs Canyon Road.

**OREGON STATE PLANE COORDINATE, North Zone NAD 83(91), International Feet Units:**

N: 698978.44  
E: 8600684.06

FIRM: Wells Surveying                      Surveyor's Seal  
P.O. Box 1696  
Pendleton, OR 97801

\1N31J-11



RENEWS: 6.30.20

20-043-C