

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla. DATE: 03/04/20.

CORNER DESIGNATION: J-13, The Southeast corner of Section 9, Township 1 North, Range 31 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC: Corner was originally established by Josiah A. Burnett under Contract No. 92 dated September 12, 1860. Notes state: Set post for corner to Secs. 9, 10, 15, and 16, drove charred stake and raised mound with trench as per instructions.

MONUMENT AND ACCESSORIES FOUND: None. Corner falls in a farmed field now in the CRP. Reestablished corner position by double proportion measurement holding the East 1/4 corner of Section 9 and the East 1/4 corner of Section 21 for latitude and the South 1/4 corners of Sections 9 and 10 for departure.

MONUMENT MARKING DETAIL:

T1N R31E
S9|S10

S16|S15
2020
54657PLS

MONUMENT SET: At the reestablished corner position, set a 2 1/2" brass cap on 1 1/4 by 30" galvanized iron pipe 30" in the ground. Cap is marked as shown in Monument Marking Detail.

New accessories:

- A silver Deep-1 magnet bears N 41° E, 32.5'.
 - A purple Deep-1 magnet bears S 38° E, 27.1'.
 - A blue Deep-1 magnet bears S 53° W, 30.8'.
 - A orange Deep-1 magnet bears N 46° W, 36.3'.
- Buried bearing object signs with the Deep-1 magnets which are buried 18" below ground line.
Used steel tape and Brunton pocket transit with 14°E declination to measure corner accessories.
Set steel fence post 2' South of corner monument with Witness sign attached.

LOCATION AND COMMENTS: Corner is located near the East edge of a CRP field about 1100' South of Coombs Canyon Road.

OREGON STATE PLANE COORDINATE, North Zone NAD 83(91), International Feet Units:

N: 699050.18
E: 8603329.42

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

Surveyor's Seal

\1N31J-13



RENEWS: 6/30/20

20-043-C