

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla. DATE: 03/11/20.

CORNER DESIGNATION: J-23, The North One-Quarter corner of Section 13, Township 1 North, Range 31 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC: Corner was originally established by Josiah A. Burnett under Contract No. 92 dated September 12, 1860. Notes state: Set post for 1/4 sec.cor. , drove charred stake and raised mound with trench as per instructions. John Kimbrell, in Survey No. 276 found in Record of Private Survey Books, surveyed through this corner. Kimbrell set a temporary point but did not recover or reestablish this corner.

MONUMENT AND ACCESSORIES FOUND: None. The corner point falls in a rocky farmed area South of a draw. The corner area is farmed down to solid rock. I searched for the 1/16 corner per Survey No. 276 to the East but did not recover it. The 1/16 th corner falls in wheat field. I reestablish this corner on the parallel of latitude by single proportion measure between the Southeast and Southwest corners of Section 12.

**MONUMENT MARKING DETAIL:**

T1N R31E  
S12  
1/4-----  
S13  
2020  
54657PLS

MONUMENT SET: Reestablished corner point is on solid rock. Set 2" Magspike with 1 1/2" aluminum disk marked "Wells Surveying 54657PLS" in hole drilled in rock and secured Magspike with lead in drill hole. This monument may be farmed out in the future, but there is no other choice for a corner monument.

**New accessories:**

A 5/8 by 24" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears N 29°58'39" E, 452.63'.

A 5/8 by 24" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears N 45°35'10" E, 484.82'.

A 5/8 by 24" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears N 11°43'53" E, 444.27'.

A 5/8 by 24" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears N 03°59'08" W, 472.09'.

Rebar accessories are set North of a draw North of the corner point. Wired bearing object signs to the corner accessories.

Bearings to the rebar accessories are State Plane Grid bearings.

LOCATION AND COMMENTS: Corner point falls in farmed wheat field in an area that has been farmed down to solid rock. There is about 2" of soil in the corner area.

OREGON STATE PLANE COORDINATE, North Zone NAD 83(91), International Feet Units:


N: 699260.73

E: 8616515.05

FIRM: Wells Surveying  
P.O. Box 1696  
Pendleton, OR 97801

Surveyor's Seal

\IN31J-23



RENEWS: 6:30:20

20-043-C