

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla. DATE: 03/06/20.

CORNER DESIGNATION: L-1, The West One-Quarter corner of Section 18, Township 1 North, Range 31 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC: Corner was originally established by David P. Thompson under Contract No. 81 dated July 8, 1859. Notes state: Set post for 1/4 Sec. Cor. And build mound of earth with pits, trench and etc., as per instructions.

MONUMENT AND ACCESSORIES FOUND: None. Reestablished corner position by single proportion measurement between the Southwest and Northwest corners of Section 18. The corner area has been previously farmed and now in CRP. There are no possessory features near the corner area.

MONUMENT MARKING DETAIL:

TIN
R30 E | R31E
1/4
S13|S18
2020
54657PLS

MONUMENT SET: A reestablished corner position, set a 2 1/2 brass cap on 1 1/4 by 30" galvanized iron pipe 30" in the ground. Brass cap is marked as shown in Monument Marking Detail.

New accessories:

- A silver Deep-1 magnet bears N 31°31' E, 30.2'.
- A purple Deep-1 magnet bears S 64°49' E, 31.6'.
- A blue Deep-1 magnet bears S 27°07' W, 27.7'.
- A orange Deep-1 magnet bears N 42°38' W, 31.3'.

Buried bearing object signs with the Deep-1 magnets which are buried 18" below ground line. Wired Witness sign to steel fence post set 2' South of corner monument.
Bearings to corner accessories are State Plane Grid bearings.

LOCATION AND COMMENTS: Corner falls on the West side of a ravine in a CRP field.

OREGON STATE PLANE COORDINATE, North Zone NAD 83(91), International Feet Units:
N: 696333.55
E: 8587019.01

FIRM: Wells Surveying Surveyor's Seal
P.O. Box 1696
Pendleton, OR 97801

\IN31L-1

