

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla. DATE: 02/27/20.

CORNER DESIGNATION: L-17, The East One-Quarter corner of Section 15, Township 1 North, Range 31 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC: Corner was originally established by Josiah A. Burnett under Contract No. 92 dated September 12, 1860. Notes state: Set a post for 1/4 Sec. Cor., drove charred stake and raised mound with trench as per instructions.

MONUMENT AND ACCESSORIES FOUND: None. Reestablished corner by single proportion measurement between the Southeast and Northeast corners of Section 15. Found remains of old fence post by corner and scattered, farmed over fence wire North and South of corner point.

MONUMENT MARKING DETAIL:

T1N R31E
1/4
S15|S14
2020
54657PLS

MONUMENT SET: At reestablished corner position, set a pointed 5/8 by 24" rebar in hole drilled into rock. Rebar is capped with a 2" aluminum cap marked as shown in Monument Marking Detail. Surrounded monument with earth and stone. Nailed a Witness sign to old fence post remains and placed post North of corner monument. Monument cap is about 6" below top of rock and earth mound.

New accessories:

A 5/8 by 15" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears N 75°14' W, 58.9'.
A 5/8 by 15" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears N 74°31' W, 28.9'.
A 5/8 by 15" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears S 05°20' E, 22.4'.
A 5/8 by 15" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears S 22°52' W, 38.1'.
Rebar accessories are in the road bank of Redwine Road. Wired bearing object signs to the rebar accessories. Bearings to accessories are State Plane Grid bearings.

LOCATION AND COMMENTS: Corner is located about 25' North of Redwine Road.

OREGON STATE PLANE COORDINATE, North Zone NAD 83(91), International Feet Units:

N: 696509.55
E: 8608648.43

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

Surveyor's Seal

\IN3L-17



RENEWS: 6/30/20

20-043-C