

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla. DATE: 03/06/20.

CORNER DESIGNATION: N-1, The Southwest corner of Section 18, Township 1 North, Range 31 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC: Corner was originally established by David P. Thompson under Contract No. 81 dated July 8, 1859. Notes state: Set post for corner to Sec's. 18, 19, 13 & 24, and build mound of earth with pits, trench and etc., as per instructions.

MONUMENT AND ACCESSORIES FOUND: None. Reestablished corner position by single proportion measurement between the Southwest corners of Sections 19 and 7. The corner area has been previously farmed and now in CRP. There are no possessory features near the corner area.

MONUMENT MARKING DETAIL:

~T1N
R30 E | R31E
S13|S18

S24|S19
2020
54657PLS

MONUMENT SET: Set a 5/8 by 24" pointed rebar 32" in the ground to refusal. Rebar is capped with a 2" aluminum cap marked as shown in Monument Marking Detail.

New accessories:

- A silver Deep-1 magnet bears N 40°14' E, 31.2'.
- A purple Deep-1 magnet bears S 64°05' E, 28.7'.
- A blue Deep-1 magnet bears S 34°11' W, 27.4'.
- A orange Deep-1 magnet bears N 41°09' W, 23.3'.

Buried bearing object signs with the Deep-1 magnets which are buried 18" below ground line. Wired Witness sign to steel fence post set 2' South of corner monument.
Bearings to corner accessories are State Plane Grid bearings.

LOCATION AND COMMENTS: Corner falls on a ridge top in a CRP field.

OREGON STATE PLANE COORDINATE, North Zone NAD 83(91), International Feet Units:
N: 693674.92
E: 8587077.16

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

Surveyor's Seal

\1N31N-1



RENEWS: 6/30/20