

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla. DATE: 02/28/20

CORNER DESIGNATION: N-13, The Southeast corner of Section 16, Township 1 North, Range 31 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC: Corner was originally established by Josiah A. Burnett under Contract No. 92 dated September 12, 1860. Notes state: Set post for cor., to Sec's. 15, 16, 21 and 22 drove charred stake and raised mound with trench as per instructions.

MONUMENT AND ACCESSORIES FOUND: None. Held record proportional latitude between the East 1/4 corners of Sections 21 and 9 with intersection of the West line of a North-South CRP field for departure to reestablish this corner. There is a pile of dumped rock gathered from adjacent fields West of the corner point.

MONUMENT MARKING DETAIL:

T1N R31E
S16|S15

S21|S22
2020
54657PLS

MONUMENT SET: At the reestablished corner position, set a 2 1/2" brass cap on 1 1/4 by 30" galvanized iron pipe 24" in the ground, marked as shown in Monument Marking Detail. Set steel fence post 3' North of monument with witness sign.

New accessories:

A 5/8 by 24" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears N 50°22' East, 48.8'.
A purple Deep-1 magnet bears S 45°10' East, 35.1'.
A 5/8 by 24" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears S 51°43' West, 31.8'.
A 5/8 by 24" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears N 51°31' West, 31.6'.
Wired bearing object signs to rebar accessories. Placed a bearing object sign with the Deep-1 magnet, which is buried 18" below ground.
Bearings to accessories are State Plane Grid bearings.

LOCATION AND COMMENTS: Corner is located at the West edge of a CRP field about 50' Southwest of a bird guzzler.

OREGON STATE PLANE COORDINATE, North Zone NAD 83(91), International Feet Units:

N: 693777.59
E: 8603410.71

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

Surveyor's Seal

\1N31N-13



RENEWS: 6:30:20

20-043-C