

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla. DATE: 02/20/20

CORNER DESIGNATION: N-15, The South One-Quarter corner of Section 15, Township 1 North, Range 31 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC: Corner was originally established by Josiah A. Burnett under Contract No. 92 dated September 12, 1860. Notes state: Set post for 1/4 Sec. Cor., drove charred stake and raised mound with trench as per instructions.

MONUMENT AND ACCESSORIES FOUND: None. Accepted fence corner with fences East and South as best remaining evidence of the original corner position. There is field berm evidence of a fence extending West, but that area is now in the CRP.

MONUMENT MARKING DETAIL:

T1N R31E
S15
1/4 -----
S22
2020
54657PLS

MONUMENT SET:

Set a 2 1/2" brass cap on 1 1/4 by 30" galvanized iron pipe 29" in the ground at the Northwest corner of a railroad tie fence corner post. Monument is marked as shown in Monument Marking Detail.

New accessories:

- A orange Deep1 magnet bears N 33° W 16.8'.
- A 5/8" by 24" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears N 89° E 18.2'.
- A purple Deep1 magnet bears S 47° W 15.2'.
- A 5/8" by 24" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears South, 15.9'.

Deep 1 magnets are buried 18" below ground with bearing object signs beside. Rebar accessories have bearing object signs wired to them.

Used Brunton pocket transit with 14° East declination and steel tape to measure accessories.

Nailed Witness sign to railroad tie fence post by corner monument.

LOCATION AND COMMENTS: Corner is located at the corner of a CRP field at fence corner with fences extending East and South.

OREGON STATE PLANE COORDINATE, North Zone NAD 83(91), International Feet Units:

N: 693816.68
E: 8606033.08

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

Surveyor's Seal

\1N31N-15



RENEWS: 6/30/20

20-043-C