

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla. DATE: 02/20/20

CORNER DESIGNATION: N-17, The Southeast corner of Section 15, Township 1 North, Range 31 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC: Corner was originally established by Josiah A. Burnett under Contract No. 92 dated September 12, 1860. Notes state: Set post for corner to Secs. 14, 15, 22 and 23, drove charred stake and raised mound with trench as per instructions.

MONUMENT AND ACCESSORIES FOUND: Accepted fence jack (crib), in old rebuilt East-West fence line as best remaining evidence of corner position. There is evidence of old fence and wire extending North and South, the wire to the North is scattered because it has been farmed over.

MONUMENT MARKING DETAIL:

T1N R31E
S15|S14

S22|S23
2020
54657PLS

MONUMENT SET: Set a 2 1/2 brass cap on 1 1/4 by 30" galvanized iron pipe 26" in the ground on the North side of fence jack and placed several stones around the monument. Monument is marked as shown in Monument Marking Detail.

New accessories:

- A 5/8 by 24" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears N 89° E, 29.3'.
- A 5/8 by 24" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears N 89° E, 16.3'.
- A 5/8 by 24" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears S 89° W, 15.4'.
- A 5/8 by 24" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears S 89° W, 27.5'.

Wired bearing object signs to accessory rebars. Used steel tape and Brunton pocket transit with 14° East declination to measure accessories. Wired a Witness sign to steel fence post just West of corner monument.

LOCATION AND COMMENTS: Corner is located in an East-West fence line approximately 1/2 mile South of Redwine Road.

OREGON STATE PLANE COORDINATE, North Zone NAD 83(91), International Feet Units:

N: 693872.92
E: 8608703.24

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

Surveyor's Seal

\1N31N-17



RENEWS: 6/30/20

20-043-C