

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla. DATE: 03/11/20.

CORNER DESIGNATION: N-23, The South One-Quarter corner of Section 13, Township 1 North, Range 31 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC: Corner was originally established by Josiah A. Burnett under C Contract No. 92 dated September 12, 1860. Notes state: Set post for 1/4 Sec. Cor. , drove charred stake and raised mound with trench as per instructions.

MONUMENT AND ACCESSORIES FOUND: None. Reestablished corner on the parallel of latitude by single proportion measure between the Southeast and Southwest corners of Section 13.

MONUMENT MARKING DETAIL:

~~T1N~~ R31E
S13
1/4 -----
S24
2020
54657PLS

MONUMENT SET: At the reestablished corner position, set a 5/8 by 24" rebar in drilled hole in rock. Rebar is 8" above ground line and surrounded with stones. Placed 2" aluminum cap on rebar, marked as shown in Monument Marking Detail. Wired Witness sign to the rebar corner monument.

New accessories:

A 5/8 by 15" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears N 46°56' E, 36.3'.
A 5/8 by 15" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears S 49°05' E, 30.1'.
A 5/8 by 15" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears S 16°26' W, 30.1'.
A 5/8 by 15" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears N 13°22' W, 38.8'.
Wired bearing object signs to the rebar accessories.
Bearings to accessories are State Plane Grid bearings.

LOCATION AND COMMENTS: Corner is located on a West facing slope that does not appear to have been farmed in past years.

OREGON STATE PLANE COORDINATE, North Zone NAD 83(91), International Feet Units:

N: 694013.12
E: 8616589.47

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

Surveyor's Seal

\1N31N-23



RENEWS: 6:30:20

20-043-C