

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla. DATE: 04/13/20.

CORNER DESIGNATION: N-7, The South one-quarter corner of Section 17, Township 1 North, Range 31 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC: Corner was originally established by Josiah A. Burnett under Contract No. 92 dated September 12, 1860. Notes state: Set a post for 1/4 Sec. Cor., drove charred stake and raised mound with trench as per instructions.

MONUMENT AND ACCESSORIES FOUND: None. The corner falls in a CRP field about 350' West of a farm road running Southeast up a ravine.

MONUMENT MARKING DETAIL:

T1N R31E
S17
1/4 -----
S20
2020
54657PLS

MONUMENT SET: I reestablished this corner position by extending the bearing and distance between the Southeast corner of Section 17 and the fence corner at the East 1/16 th corner on the South line of Section 17 Westerly the same bearing and distance. The fence line running North from the East 1/16 th corner on the South line of Section 17 extends 1 1/4 mile to the North. At the reestablished corner position, set a 2 1/2" brass cap on 1 1/4 by 30" galvanized iron pipe 28" in the ground. Set a steel fence post 2' South of corner with Witness sign attached.

New accessories:

- A silver Deep-1 magnet bears Grid Azimuth 01°18', 34.1'.
 - A purple Deep-1 magnet bears Grid Azimuth 131°37', 26.5'.
 - A blue Deep-1 magnet bears Grid Azimuth 202°27', 37.4'.
 - A orange Deep-1 magnet bears Grid Azimuth 302°13', 31.7'.
- Buried bearing signs with the Deep-1 magnets which are buried 18" below ground line.
Azimuths to accessories are State Plane Grid azimuths.

LOCATION AND COMMENTS: Corner is located in a CRP field about 350' West of a road running Southeast up a ravine.

OREGON STATE PLANE COORDINATE, North Zone NAD 83(91), International Feet Units:

N: 693734.08
E: 8595558.24

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

Surveyor's Seal

\1N31N-7



RENEWS: 6/30/20

20-043-c