

OREGON CORNER RESTORATION FORM

Section 25 Township 1 N Range 32 EWM  
County Umatilla Date 10 October 2004

V-23

CORNER DESIGNATION

S  $\frac{1}{4}$  Section 25

- Condition Report Only
- Not Found
- Renewed
- Unrecorded
- Surveyed In
- Referenced Out

Previous Renewals/Surveys, etc.

Original survey - David Chapman Contract 107, Sept. 21, 1864  
Resurvey - Zenas F. Moody Contract 164, October 4, 1871


Monument(s) & Accessories Found: (Condition and Source)

Fence Intersection East-West and South

Chapman set a Stone, and Moody set a Post and dug pits. No evidence of either were found.

Monument Detail

Sketch



**2 1/2" BRASS CAP  
ON 1 1/2" X 30"  
IRON PIPE**

Monument Set (Procedures and Description)

Set Brass cap at Fence Intersection.  
Set 5/8" X 30" Iron Rebar w/ Alum. Cap stamped PLS 933  
15 Feet North East South and West.

New Accessories

Location sign on Fence Corner at Southwest Corner of Section

Location & Comments

The West line of the Section if 1 1/2 miles South of Spring Cr. Rd. Compass Declination Firm/Agency  
Krumbein Engineering Address 361 S.E. 2nd  
Pendleton, OR. 97801 Party Chief David Krumbein  
Notes  
Witness

Surveyor's Seal

