

# Record of Corner Monumentation

*K-17*  
**History of original corner establishment:**

W 1/16 corner Section 14, was monumented by C.E. Redfield during his 1919 circa. He set a 2 ½" brass cap on a 36" pipe in a plowed field.

**Description of corner evidence found:**

I found no trace of this monument as it is located in a field that has been farmed for many years. No doubt the monument has been destroyed during farming operations.

**Description of monument and accessories I established to perpetuate the original location of this corner:**

I set a 2 ½" Aluminum Cap on a 36" pipe and being stamped as shown in the diagram. I buried the pipe 32" in the ground and placed a large mound of stone around the monument. I also placed a steel fence post in the mound of stone to aid in locating the monument in the future.

**Diagram:**

W 1/16  
S 14  
T 1 N R 33 E  
2003  
ORLS 645

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*James H. Hambleton*

02-20-03

OREGON  
JULY 17, 1964  
JAMES H. HAMBLETON  
645

03-35-B