

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 05/25/05

CORNER DESIGNATION: 1N33EL11, The center one-quarter corner of Section 16.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner was reported established by James P. Currin, under Contract No. 537. Notes state: Set basalt stone, 9x8x7 inches, marked "1/4" on North face.

I find no record of recovery or re-establishment or recovery by C.E. Redfield, U.S. Indian Service Surveyor, in the available Redfield Notes..

MONUMENT AND ACCESSORIES FOUND: None. Corner falls in wheat fields.

MONUMENT MARKING DETAIL: See "Monument Set" below.

MONUMENT SET:

Corner position was searched based on the "Three Mile Rule". Nothing was found. Corner was re-established by the "Three Mile Rule", between the East and West one-quarter corners of Section 16. At position established by survey, set a 5/8" x 30" rebar, with cap 8" below ground surface, in East-West field line. Yellow plastic cap is marked "OR PLS 1106, WA PLS 17372".

New accessories:

- A silver deep-1 magnet bears North 33° East, 37.5 feet.
- A purple deep-1 magnet bears South 45° East, 42.9 feet.
- A blue deep-1 magnet bears South 48° West, 39.0 feet.
- An orange deep-1 magnet bears North 36° West, 47.9 feet.

All deep-1 magnets are buried 18" below ground level with bearing object signs buried with them.

Set steel fence post 0.5 feet West of monument with "witness" sign attached.

LOCATION AND COMMENTS: Corner is located on an East-West field line, in wheat fields.

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

1N33L11

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-06

RECEIVED BY
Umatilla County Surveyor
Date 6-05
Rec'd By KK
No. 05-125-B