

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 05/14/08

CORNER DESIGNATION: 1N34, V-13, The Northwest Corner of Section 34.

**PREVIOUS RENEWALS/SURVEYS ETC.:**

Corner was established by Currin and Noland under Special Contract date May 4<sup>th</sup>, 1887. Original notes state: Set a post 4ft. long 4 in. Sq. 2 feet in the ground marked T1N R34E S27 on NE, S28NW, S33SW, S34SE, 1 notch on South and 3 notches on East edges for Cor. to Sections 27, 28, 33, 34; from which a pine 18 in. diam. bears North 85° West dist. 72 lks marked T1N R34E S28 BT, pine 12 in. diam. bears South 60° West dist. 70 lks marked S33 BT, pine 20 in. diam. bears North 82° East dist. 228 lks marked S27 BT, no other trees. The corner was reported as recovered on John Kimbrell's Survey No. 162, in April-May, 1903.

**MONUMENT AND ACCESSORIES FOUND:**

Reestablished corner point from remains of the three original bearing trees, now decayed and burnt pine stumps. No scribe marks remain. The bearings and distances from the stumps fit well, considering the steep slope.

**MONUMENT MARKING DETAIL:**

T1N R34E  
S28|S27  
S33|S34  
2008  
PLS 1106

**MONUMENT SET:**

At the reestablished corner point, set a 2 3/8 " brass cap on 1 1/4" x 30" galvanized iron pipe, 24" in the ground and surrounded with a mound of earth, from which:

Decayed and burnt Ponderosa pine stump bears N 85°W, 49.9'.

Decayed and burnt Ponderosa pine stump bears S 60°W, 46.2'.

Decayed and burnt Ponderosa pine stump bears N 82°E, 152.3'.

Measured from where face of blaze would have stood on the original bearing trees.

New accessories:

A 14" Ponderosa pine scribed T1N R34E S27 BT on single blaze bears N 27° E, 23.9 feet.

A 15" Ponderosa pine scribed T1N R34E S34 BT on single blaze bears East, 26.5 feet.

A 4" Douglas fir scribed "X" at breast height and BT at base on double blaze bears S 12° E, 22.6 feet.

A 5" Ponderosa pine scribed "X" at breast height and BT at base on double blaze bears S 28°W, 35.3 feet.

Nailed bearing object signs to all new bearing trees and nailed a brass washer stamped "PLS 1106" to lower part of blazes. Set steel fence post South of monument with "Witness" sign.

**LOCATION AND COMMENTS:** Corner is located approximately 100' North of the top of a ridge on steep North slope.

OREGON STATE PLANE COORDINATE, North Zone, NAD

83(CORS96)(EPOCH:2002.0000), International Feet:

N = 685212.94 Coordinates by OPUS solution position.

E = 8699397.24

FIRM: William R. Wells, PLS

P.O. Box 1696

Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

1N34V13

RECEIVED BY  
Umatilla County Surveyor  
Date 7-08  
Rec'd By KK  
BY 08-97-P

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*renews 6-30-08*