

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 5/12/08

CORNER DESIGNATION: 1N34, X-11, The Center One-Quarter Corner of Section 33.

PREVIOUS RENEWALS/SURVEYS ETC.: I find no record this corner was previously established.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL: See below.

MONUMENT SET:

At the corner point, set a 5/8" x 24" iron rebar, with 1/14" red plastic cap marked "ORPLS 1106 WAPLS 17372" flush with the ground. Set steel fence post with witness post sign attached 1 foot South of corner monument.

New accessories:

A 5/8"x24" iron rebar with 1 1/4" red plastic cap marked "ORPLS 1106 WAPLS 17372" bears North 14°13'23" West, 443.78 feet. (This is a corner on the division line between Parcels 1 and 2 of Partition Plat filed separately from this corner record.)

A 5/8"x24" iron rebar with 1 1/4" red plastic cap marked "ORPLS 1106 WAPLS 17372" bears North 28° West, 134.2 feet. Attached bearing object sign to rebar.

A 5/8"x24" iron rebar with 1 1/4" red plastic cap marked "ORPLS 1106 WAPLS 17372" located in North-South fence line bears North 39° West, 76.1 feet. Attached bearing object sign to rebar.

A 5/8"x24" iron rebar with 1 1/4" red plastic cap marked "ORPLS 1106 WAPLS 17372" located in North-South fence line bears South 65° West, 52.9 feet. Attached bearing object sign to rebar.

LOCATION AND COMMENTS:

Corner falls in a mountain hay field approximately 48' East and 151' South of a fence corner with fences East and South.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(CORS96)(EPOCH:2002.0000), International Feet:

N = 682500.24 Coordinates by OPUS solution method.
E = 8696786.32

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801


COMPASS DECLINATION: 18° East Surveyor's Seal

Witnesses: Jason Wells, LSIT

1N34X11



William R. Wells



renews 6-30-08

RECEIVED BY

Umatilla County Surveyor

Date 7-08

Rec'd By KK

BY: A 8-99-0