

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla. DATE: 08/18/09.

CORNER DESIGNATION: X-1, The West One Quarter Corner of Section 31, Township 1 North, Range 35 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC: Corner originally established by established by Currin and Noland under Special Contract dated May 4, 1887. Original notes state: "Set basalt stone 20x12x12 ins., 15 ins. in the ground mkd. 1/4 on W. face from which: A pine 20 ins. in diam. brs. N 52 1/2° W, 43 lks. mkd. 1/4 S BT. No other trees in limits. Raised mound of stone alongside corner, Pits impracticable." A monument was established for this corner under Survey No. 03-274-C in 1975. In re-establishing this corner the original stone monument at the NW Corner of Section 31 was not recovered, map states only bearing trees were found. The original corner stone at the NW Corner was subsequently recovered under Survey No. 95-169-B.

MONUMENT AND ACCESSORIES FOUND: None. Corner was reestablished at mid-point between the recovered Northwest and Southwest Corners of Section 31. A thorough search was made for the original stone and bearing tree. Corner area is very steep and has been logged. We found a pine stump at the approximate location of the original bearing tree, but could not verify it was the original bearing tree because it was cut low, below where scribes would have existed.

MONUMENT MARKING DETAIL:

TIN  
R34E 1/4 R35E  
S36|S31  
2009  
PLS 1106

MONUMENT SET: At the re-established corner position, set a 5/8" by 24" iron rebar with a 2" aluminum cap in a 4 foot diameter mound of stone. Cap is marked as shown in "Monument Marking Detail".

New accessories:

- A 2 1/2" brass cap on a 2" galvanized iron pipe with cap 12" above ground level per Survey No. 03-274-C bears S 17°15' E, 3.8 feet.
- A 24" Douglas fir bearing tree with scribing visible on double blaze bears S 07° E, 27.4 feet, there is no record for this bearing tree.
- A 12" Douglas fir scribed 1/4 S36 BT on a single blaze with a 3/4" brass washer stamped "PLS 1106" nailed to it bears N 58° W, 30.2 feet.
- A 60 penny nail driven vertically into a pitched stump of a 24" Ponderosa pine 18" above ground level bears N 50° W, 27.2 feet.

Set steel fence post with attached witness sign near new monument. Attached bearing object signs to all bearing trees.

LOCATION AND COMMENTS: Corner is located in a 4 foot dia. mound of stone on a steep hillside. Corner is on a steep hillside about 25 feet West of a deep ravine.

FIRM: Wells Surveying  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East


Witnesses: Jason Wells, LSIT  
Eddie Kilner

\N35X-1

Surveyor's Seal



*renews 6-30-10*



*09-118-R*