

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 05/12/08

CORNER DESIGNATION: 1N34, X-9, The West One-Quarter Corner of Section 33.

PREVIOUS RENEWALS/SURVEYS ETC.:

Corner was originally established by Currin and Noland under Special Contract dated May 4th, 1887. Original notes state: Set basalt stone 10x8x7, 7ins. in the ground marked 1/4 on West face for 1/4 Sec.Cor. and raised mound of stone over it.

MONUMENT AND ACCESSORIES FOUND: None. Corner was searched on four separate occasions, without success. Corner falls on a steep South slope, in a area with many rocks and stones.

MONUMENT MARKING DETAIL:

T1N R34E
1
4
S32 | S33
2008
PLS 1106

MONUMENT SET:

Re-established corner by single proportionate measure holding the established Section Corners North and South. Set a 2" aluminum cap on 5/8"x24" iron rebar 15" in the ground to bedrock and surrounded with a mound of stone and earth. Monument marked as shown in monument marking detail.

New accessories:

A 5/8"x24" iron rebar with 1 1/4" red plastic cap stamped "ORPLS 1106 WAPLS 17372" bears North 34° East, 26.1 feet.

A 5/8"x24" iron rebar with 1 1/4" red plastic cap stamped "ORPLS 1106 WAPLS 17372" bears South 48° East, 30.5 feet.

A 5/8"x24" iron rebar with 1 1/4" red plastic cap stamped "ORPLS 1106 WAPLS 17372" bears South 60° West, 24.3 feet.

A 5/8"x24" iron rebar with 1 1/4" red plastic cap stamped "ORPLS 1106 WAPLS 17372" bears North 41° West, 34.5 feet.

Attached bearing object signs to all rebar accessories.

LOCATION AND COMMENTS: Corner is located on a steep rocky Southerly slope 200+/- feet Northerly from the bottom of a draw.

OREGON STATE PLANE COORDINATE, North Zone, NAD

83(CORS96)(EPOCH:2002.0000), International Feet:

N = 682442.76 Coordinates by OPUS solution method.

E = 8694136.65

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

1N34X9

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-08

RECEIVED BY
Umatilla County Surveyor
Date 7-08
Rec'd By KK
w. 10-98-P