

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 9/19/94

CORNER DESIGNATION: Z-9. Southeast corner Section 32, T1N., R34E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Most recent approved GLO Survey was made by James P. Currin and James Noland, under Special Contract dated May 4, 1887. Notes state: "Set basalt stone, 12 x 12 x 12 ins., 8 ins. in the ground, for cor to secs. 32 and 33 marked S C with 4 notches on E., and 2 notches on W. edges, from which: A pine, 16 ins., bears S.45°W., 300 lks. dist., marked 1/4 (as per GLO notes) S S C. B. T. Raised a mound of stone over it."

MONUMENT AND ACCESSORIES FOUND: None. Corner re-established by single proportionate measurement between the re-established South 1/4 corner Section 31 and the recovered South 1/4 corner Section 33, using James P. Currin and James Noland records under GLO Contract dated May 4, 1887.

**MONUMENT MARKING DETAIL:**

T1N R34E  
S32 | S33  
-----  
SC  
T1S R34E  
1994  
PLS 1106

MONUMENT SET: At position determined by survey set a 2 1/2" brass cap on a 1 1/4" x 30" galvanized iron pipe, 27" in the ground, with mound of earth to cap, (marked as shown in the monument detail).

**New Accessories:**

Set steel fence post with witness sign attached 1.6 feet North of monument.  
A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106" bears N 83° W-17.8 feet.  
A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106" bears N 51 1/2° W-10.6 feet.  
A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106" bears N 39° E-11.5 feet.  
A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106" bears N 68° E-17.2 feet.  
Attached bearing object signs to each iron pin. Set a steel fence post near each iron pin with witness sign attached.

**LOCATION & COMMENTS:**

**STATE PLANE CO-ORDINATE:**

Oregon North Zone, NAD 83/91, U.S. Survey Foot:  
N = 679755.72  
E = 8694168.12

COMPASS DECLINATION: 18° East.

Surveyor's Seal

FIRM/AGENCY: William R. Wells, PLS  
P.O. Box 1696  
Pendleton, Oregon 97801

Party Chief: Robert D. English  
Notes: Robert D. English  
Witness: F. Scot Munro

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Will: R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

Renews 6/30/96

RECEIVED BY  
Umatilla County Surveyor  
Date 2-95  
Rec'd By KB  
No. 95-16-C