


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

HISTORY OF ORIGINAL CORNER ESTABLISHMENT:

Corner originally established by Marius Buchanan under GLO contract number 635, dated April 19, 1895. Surveyor General record states:
Set a tamarac post 3 ft. long, 3ins. square, 24 ins. in the ground for 1/4 sec. cor. marked 1/4 S on N. face, from which:
A pine 16 ins. diam. bears N. 30 3/4° E. 51 lks. dist. marked 1/4 S BT.
A pine 8 ins. diam. bears S 10 1/2° W. 101 lks. dist. marked 1/4 S. BT.

T 1 N R 35 E R-15



Corner searched for and not found by Gary Wagner in survey 05-181-B

Corner searched for and not found by William R. Wells in survey number 06-509-B.

DESCRIPTION OF CORNER EVIDENCE FOUND:

None.

DESCRIPTION OF MONUMENT AND ACCESSORIES I ESTABLISHED

TO PERPETUATE THE ORIGINAL LOCATION OF THIS CORNER:

At proportionate position, I set a 2 1/2" x 30" aluminum pipe with 2 1/2" aluminum cap, marked as shown below, 28 inches in the ground, in a collar of stone 1 1/2 ft. in diameter, from which:

An 8 inch Western Larch bears North 41° East, a distance of 136.95 feet, marked 1/4 S22 BT.
A 6 inch White Fir bears South 44° East, a distance of 29.00 feet, marked 1/4 S27 BT.
A 12 inch Lodgepole Pine bears South 57° West, a distance of 38.60 feet, marked 1/4 S27 BT.
A 10 inch pistol butted White Fir bears North 52° West, a distance of 42.55 feet, marked 1/4 S22 BT.

I set a steel fencepost approx. 1 foot East of corner monument.
I hereby certify that the corner was monumented on November 8, 2012.

Witness: Rick Robinson

REGISTERED
PROFESSIONAL
LAND SURVEYOR



OREGON
June 2, 2010
JEFFERY S. HSU
83571

Renewal Date: June 30, 2013

BAGETT - GRIFFITH & BLACKMAN

T1N R35E

1/4 S 22
S 27

2012

OPLS 83571

RECEIVED BY

Umatilla County Surveyor
Date: 12/14/2012
Rec'd By: [Signature]
No.: 12-145-B

I used a steel tape and magnetic compass in the establishment of trees. I used 16° East magnetic declination. Distances are to a 60d spike in the right hand side of the new trees. Bearing is to a brass washer marked OPLS 83571 in the lower BT blaze.