

Section Corner $\frac{30}{31} | \frac{29}{32}$

V-5

Original:

Var. $20\frac{1}{2}^{\circ}$

Set basalt stone 9"x8"x7", 6" in ground for corner 29, 30, 31 and 32. 1 notch on south and 5 notches on east edges.

10" pine N75°E, 72 links, "T1N R35E S29 BT". (Parks Crew found 24" ponderosa pine at fence corner.)

18" pine S76°E, 138 links, "T1N R35E S32 BT". (Parks Crew found 31" ponderosa pine.)

The faces, though well grown over, were obvious and were not chopped out.

Parks Crew Set:

At the intersection of the distances from the bearing trees a 5/8"x30" capped iron rod marked "Oregon State Parks" and erected mound of rock around rod.

9" ponderosa pine S4°30'W, 11.2' to center, scribed "T1N R35E S31 BT".

17" ponderosa pine N36°15'W, 99.8' to center, scribed "T1N R35E S30 BT RS691".

Witnessed by:

A. Slack
R. Hemmer
L. Boge
S. Morrison

$\frac{1}{4}$ Corner Section 29 and 30 T-5

Original:

Var. $20\frac{1}{2}^{\circ}$

Set post 3' long, 3" square, 24" in ground, marked " $\frac{1}{4}$ S" on west face.

36" red fir N45°W, 29 links " $\frac{1}{4}$ S BT". (Parks Crew found 37" rotted red fir stump with "BT" visible, set corner record bearing and distance from this tree.)

12" pine S69°E, 80 links " $\frac{1}{4}$ S"BT". (Parks Crew found rotted pine stump S66°E, 56.8' to center.

Parks Crew Set:

5/8"x30" capped iron rod marked "Oregon State Parks".

16" fir S82°E, 33.3' to center, scribed "W $\frac{1}{4}$ S29 BT". Set Parks corner tag.

12" fir N6°W, 24.5' to center, scribed "E $\frac{1}{4}$ S30 BT RS691".

Corner is approximately 8 feet west of a north-south fence line.

Witnessed by:

R. Hemmer
L. Boge
L. Hettema

Center $\frac{1}{4}$ Section 29 T-7

Parks Crew Set:

5/8"x30" capped iron rod marked "Oregon State Parks".

RECEIVED BY

Umatilla County Surveyor

Date 11-81

Rec'd by BLS

No. S-124

Emigrant Springs State Park Survey
Section 29, T1N, R35E, W.M.
August 28, 1981
Page 6

7' steel post with white boundary paddle marked "Oregon State Park Boundary Do Not Disturb", 2.0' northeast of iron rod.

17" fir N29½°E, 77.3' to center, scribed "C½ S29 BT". Set Parks corner tag.


Power pole N57½°W, 68.8' to center.

Corner of new fence S84°E, 33.2'.

Corner monument is located in a newly cleared area of gas pipeline.

Witnessed by:

A. Slack
R. Hemmer
L. Boge
S. Morrison


John E. Hollingsworth

John E. Hollingsworth
Oregon State Parks
525 Trade Street SE
Salem, OR 97310

RECEIVED BY
Umatilla County Surveyor
Date 11-21
Rec'd by BLS
No. S-124