

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 08/12/09.

CORNER DESIGNATION: X-3, the Center One-Quarter Corner of Section 31, Township 1 North, Range 35 East, W.M., Umatilla County, Oregon.

PREVIOUS RENEWALS/SURVEYS ETC: A monument for this corner was established in 1975 under Survey No. 03-274-C. According to the survey, the Northeast Corner, Southeast Corner and South 1/4 Corners of Section 31 were not recovered in establishing this monument. Original evidence of those corners has been recovered subsequent to Survey No. 03-274-C.

MONUMENT AND ACCESSORIES FOUND: Found 2 1/2" brass cap on galvanized iron pipe with cap stamped "T1N R35E, C 1/4, S31, 1975, PE 8508". This monument was not held because of subsequent recovery of original corner evidence controlling the corner position.

MONUMENT MARKING DETAIL:

T1N R35E
C 1/4
.
S 31
2009
PLS 1106

MONUMENT SET: Corner position was determined by survey as shown on the accompanying Record of Survey. At the corner point, set a 2" aluminum cap on a 5/8" x 24" rebar with cap 4" above ground level and stamped as shown in "Monument Marking Detail".

New accessories:

A 6" western larch scribed "X" at breast height and "BT" at base on double blaze bears South 74° West, 82.9 feet.

A 18" Ponderosa pine with scribing visible on double blaze bears South 11° West, 21.1 feet. Found no record for this bearing tree.

The rejected monument per Survey No. 03-274-C, a 2 1/2" brass cap on 2" galvanize iron pipe projecting 8" above ground level, bears N 27° 16' W, 3.7 feet.

A 14" Ponderosa pine scribed "C1/4 S31 BT" on single blaze bears North 09° West, 25.9 feet.

Attached bearing object signs to all bearing trees. Set steel fence post 1 foot East of monument with witness sign.

LOCATION AND COMMENTS: Corner located on flat timbered ridge in scattered timber.

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Witnesses: Jason Wells, LSIT
Eddie Kilner

\IN35X3

Surveyor's Seal
**REGISTERED
PROFESSIONAL
LAND SURVEYOR**
William R. Wells
**OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106**
renews 6-30-10