


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

x-9

History of original corner establishment:

The corner was originally established by Currin and Nolin under special contract dated May 4, 1887. The notes state that at the corner a 3 foot long by 3 inch square post was set 24 inches in the ground from which:



- A 6" Pine bears S10°E - 29LK marked 1/4 S BT.
- A 10" Tamarack bears N73°W - 72LK marked 1/4 S BT.

x-9

Description of corner evidence found:

NONE - Corner was re-established by single-proportionate measure.

Description of monument and accessories established to perpetuate the original location of this corner:

Set 2" x 30" Iron pipe with brass cap 24" in the ground from which:


- A 9" Western Larch bear S55°W-9.1 feet scribed 1/4 S32BT.
- A 10" Ponderosa Pine bears S51°E-55.7 feet scribed 1/4 S33BT.

Used staff compass with 20° East declination and measured to the center of the bearing trees.

Corner was set June 4, 1983

Witness: Stanley G. Wallulis

Cap is Marked:



**REGISTERED  
PROFESSIONAL  
LAND SURVEYOR**

*William R. Wells*

OREGON  
JULY 22, 1977  
**WILLIAM R. WELLS**  
1106

Office of Surveyor County of Umatilla  
 State of Oregon, I hereby certify that the within instrument was filed in this office  
 for record on the 22<sup>nd</sup> day of Feb, 1985  
 by Billy Cochran  
 (COUNTY OFFICIAL) (DEPUTY)

**RECEIVED BY**  
 Umatilla County Surveyor  
 Date \_\_\_\_\_  
 Rec'd By \_\_\_\_\_  
 No. 85-11-A