

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 9/9/94

CORNER DESIGNATION: Z-21. Southeast corner Section 35, T1N., R35E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Most recent approved GLO Survey was made by James P. Currin and James Noland, under Special Contract dated May 4, 1887. Notes state: "Cor. is a post 4 ft. long, 4 ins. square, 24 ins. in the ground, well preserved, marked S.C.T1NR35E on N.; S36 on E and S35 on W faces with 1 notch on E. and 5 notches on W edges, from which: A Tamarack 12 ins. in diam. bears N60°E 7 lks. dist., marked S.C.T.1 N.R.35E.S.36 B.T. A Tamarack 12 ins. in diam. bears S25° W.18 lks. dist., marked S.C. T1S.R.35E. B.T. A Pine, 12 ins. in diam. bears N.50°W.36 lks. dist., marked S.C.T1NR35E.S35.B.T. The first above named tree being dead, I marked instead, A Pine, 10 ins. in diam. bears N60°E. 15 lks. dist. S.C.T.1 N.R.35 E. S36 B.T." This corner was originally established by Timothy Davenport under Contract No. 102, dated July 20, 1863.

MONUMENT AND ACCESSORIES FOUND:

A 12" m/l diameter rotten pine stump, bears N 55° W-24.6 feet, with visible axe marks and burnt out blaze (Davenport bearing tree).
A 12" m/l diameter rotten pine stump, bears N 47° E-5.4 feet, with visible scribing 'BT' (Currin and Nolan bearing tree).
A 12" m/l diameter rotten tamarack stump, bears S 20° W-13.0 feet, totally rotten (Davenport bearing tree).
Reset corner position at average position determined by measurement from original bearing tree remains.

MONUMENT MARKING DETAIL:

T1N R35E
S35 | S36

S1
T1S R35E
1994
PLS 1106

MONUMENT SET:

At re-established corner position, set 2 1/2" brass cap on 1 1/4" x 30" galvanized iron pipe, 24" in the ground, with mound of earth to cap, (marked as shown in monument detail).

New Accessories:

Set steel fence post 2.2 feet North of monument with witness sign attached.

A 21" douglas fir bears N 46° W-41.9 feet, scribed: T1N R35E S35 SC BT.

A 9" tamarack bears N 07° W-47.3 feet, scribed: T1N R35E S35 SC BT.

A 9" tamarack bears N 21° E-51.4 feet, scribed: T1N R35E S36 SC BT.

A 8 1/2" tamarack bears N 65° E-34.0 feet, scribed: T1N R35E S36 SC BT.

Bearing trees have a brass washer stamped 'PLS 1106' nailed to the face of the blaze. Attached bearing object and witness signs to each tree, painted a 6" band and face of blaze red.

LOCATION & COMMENTS:

STATE PLANE CO-ORDINATE:

Oregon North Zone, NAD 83/91, U.S. Survey Foot:

N = 680925.97
E = 8741945.80

RECEIVED BY
Umatilla County Surveyor
Date 2-95
Rec'd By KK
No. 95-16-C

COMPASS DECLINATION: 18° East.

Surveyor's Seal

FIRM/AGENCY: William R. Wells, PLS
P.O. Box 1696
Pendleton, Oregon 97801

Party Chief: Robert D. English
Notes: Robert D. English
Witness: F. Scot Munro

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Renews 6/30/96

RECEIVED BY

Umatilla County Surveyor

Date 2-95

Rec'd By KK

No. 95-16-C