

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 8/2/94

CORNER DESIGNATION: Z-5. Southeast corner Section 31, T1N., R35E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Most recent approved GLO Survey was made by James P. Currin and James Noland, under Special Contract dated May 4, 1887. Notes state: "Set post 4 ft. long, 4 ins. square, 24 ins. in the ground in exact place of original cor. for cor. to secs. 31 and 32, marked S.C.T.1 N.R.35E. on N., S32 on E. and S.31 on W. faces with 5 notches on E. and 1 notch on W. edges, from which: A Pine, (original bearing tree) 26 ins. in diam. bears N.10°E. 43 lks. dist., marked S.C.T.1N.R.35 E. S.32 B.T. A Pine, 6 ins. in diam. bears S.10°W. 10 lks. dist. marked S.C.T.1 S.R.35 E. B.T. A Red Fir, 24 ins. in diam. bears N50°W. 103 lks. dist., marked S.C.T.1 N.R. 35 E. S31 B.T. The other old bearing tree is fallen." Reference to the original corner and bearing trees are from survey made by Timothy Davenport, under Contract No. 102, dated July 20, 1863. Re-monumented by PLS 1099 in 1983, in survey No. 83-185-R.

MONUMENT AND ACCESSORIES FOUND: Found 2 1/2" brass cap on a 2 1/2" aluminum pipe, protruding 2" out of the ground, (marked as shown in the monument detail).

Bearing Trees:

- A 16" douglas fir bears N 36 1/2° E-58.0 feet, with mostly healed over blaze, (LS 1099 bearing tree).
- A 14" western larch bears S 11° E-6.8 feet, pitched and healed over blaze, (LS 1099 bearing tree).
- A 13" douglas fir bears S 59° W-19.6 feet, pitched over, blaze, (LS 1099 bearing tree).
- A 17" white fir bears N 43° W-68.4 feet, with visible scribing, (LS 1099 bearing tree).
- A 24" pine stump bears N 06° E-29.5 feet, with visible scribing, (Davenport bearing tree).

MONUMENT MARKING DETAIL:

T1N
 SC
 S31 | S32 R
 ----- 35
 S6 | S5 E
 T1S
 PLS 1099
 1983

MONUMENT SET:

New Accessories:

Set a steel fence post 3 feet West of monument, with witness sign attached.

LOCATION & COMMENTS: Corner in edge of logged area.

STATE PLANE CO-ORDINATE:

Oregon North Zone, NAD 83/91, U.S. Survey Foot:
N = 680403.52
E = 8720670.24

COMPASS DECLINATION: 18° East.

Surveyor's Seal

FIRM/AGENCY: William R. Wells, PLS
P.O. Box 1696
Pendleton, Oregon 97801

Party Chief: Robert D. English
Notes: Robert D. English
Witness: F. Scot Munro

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

RECEIVED BY

Umatilla County Surveyor

Date 2-95

Rec'd By KK

No. 95-16-C

Renews 6/30/96