

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established in 1882 by Herman D. Gradon, US Deputy Surveyor, under Contract Number 452. The Surveyor General's records state:

Set a basalt stone 15x8x4 ins. 10 ins. in the ground for 1/4 sec. cor. marked 1/4 on W-face and raised a mound of stone alongside.

The 1/4 section was monumented in 1998, by Kaiser/Griffin/ Seibold, Cadastral Surveyors under Bureau of Land Management Group No. 1844. The field notes state:


Point for the 1/4 sec. cor. of secs. 6 and 5, at proportionate distance; there is no remaining evidence of the original corner.

Set a stainless steel post, 28 ins. long, 2-1/2 ins. diam., 6 ins. in the ground, to solid rock, and supported in a mound of stone, 4 ft. base to top, with brass cap, from which:

A ponderosa pine, 17 ins. diam., bears N.57-1/2°E., 192 lks. dist., mkd. 1/4 S6 and S5 BT.

No bearing trees available within limits in sec. 6.

Deposited a magnet in a white plastic case at the base of the stainless steel post.



Description of corner evidence found:

Found 3-1/4" BLM brass cap marked per the diagram in fallen apart rock mound. Monument is firmly set and leaning slightly to the south. From which:

17" Ponderosa Pine bears N.58°E., 126.7 feet, growing out of large rock outcrop with visible scribing.

Description of monument and accessories I established to perpetuate the original location of this corner:

We rebuilt the rock mound and established the following references:

5/8 x 24 inch rebar with 1-1/2" aluminum cap, bears West, 23.4 feet, stamped WSI/RM 23.4, 2535.

5/8 x 24 inch rebar with 1-1/2" aluminum cap, bears East, 25.0 feet, stamped WSI/RM 25.0, 2535.

5/8 x 24 inch rebar with 1-1/2" aluminum cap, bears S.14°W., 20.6 feet, stamped WSI/RM 20.6, 2535.

Reference monuments have an arrow pointing towards the corner. Appropriate signs have been attached to all bearing trees as required by this US Forest Service contract. 20° declination was used. Fieldwork was performed in July and August 2002.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Michael P. LeJeune

OREGON 11/06/02
JAN. 21. 1992
MICHAEL P. LE JEUNE
2535

EXPIRES 12/31/02

Prepared by: White Shield, Inc.
2515 W. Falls Ave.
Kennewick, WA 99336

Michael P. LeJeune,
Oregon PLS. 2535

Office ofCounty Surveyor....., County ofUmatilla.....,State of Oregon, I hereby certify that the within instrument was filed in this office for record on theday of

David H. Allen
(County Official)

RECEIVED BY

Umatilla County Surveyor
Date 11-02
Rec'd By KK
No. 02-273-B

(Deputy)