

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:


The corner was monumented in 1998, by Kaiser/Griffin/ Seibold, Cadastral Surveyors under Bureau of Land Management Group No. 1844. The field notes state:

Point for the center 1/4 sec. cor. of sec. 5, at intersection with the E. and W. centerline.

Set a stainless steel post, 28 ins. long, 2-1/2 ins. diam., 22 ins. in the ground, with brass cap from which:

A Douglas fir, 17 ins. diam., bears S.62-1/2°E., 69 lks. dist., mkd. C 1/4 S 5 BT. A ponderosa pine, 16 ins. diam., bears S.04-1/2°W., 72 lks. dist., mkd. C 1/4 S5 BT.

Deposited a magnet in a white plastic case at the base of the stainless steel post.



Description of corner evidence found:

Found 3-1/4" BLM brass cap marked per the diagram, 0.2 feet above ground.

18" Douglas fir bears S.62°30'E., 45.5 feet (BLM Bearing Tree).

16" Ponderosa pine S.14°30'W. 47.5 feet (BLM Bearing Tree).

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 5/8 x 24 inch rebar with 2 inch aluminum cap, bears East 33.2 ft, stamped WSI/RM 33.2, 2535.

Set 5/8 x 24 inch rebar with 1-1/2 inch aluminum cap, bears West 50.0 ft, stamped WSI/RM 50.0, 2535.

Reference monuments have an arrow pointing towards the corner. Appropriate signs have been attached to all bearing trees as required by this US Forest Service contract. 20° declination was used. Fieldwork was performed in July and August 2002.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Michael P. LeJeune

OREGON 11/06/02
JAN. 21, 1992
MICHAEL P. LE JEUNE
2535

Expires 12/31/02

Prepared by: White Shield, Inc.
2515 W. Falls Ave.
Kennewick, WA 99336

Michael P. LeJeune,
Oregon PLS. 2535

Office ofCounty Surveyor....., County ofUmatilla.....,State of Oregon, I hereby certify that the within

instrument was filed in this office for record on theday of

David H. Le...
....., by
(County Official)

RECEIVED BY
Umatilla County Surveyor
(Deputy) Date 11-02
Rec'd By KK
No. 02-273-B