

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established in 1998, by Kaiser/Griffin/ Seibold, Cadastral Surveyors under Bureau of Land Management Group No. 1844. The BLM records state:

Point for the center N1/16 sec. cor. of sec. 9.


Set a stainless steel post, 28 ins. long, 2-1/2 ins. diam., 22 ins. in the ground, with brass cap, from which:

A ponderosa pine, 22 ins. diam., bears N.34°W., 253 lks. dist., mkd. CN 1/16 S9 BT.

No other bearing trees available within limits.

Deposited a magnet in a white plastic case at the base of the stainless steel post.

From this point, the cor. of wire fences extending S. and W., bears S.41-1/4°W., 2,780 chs. dist.



Description of corner evidence found:

Found 3-1/4" BLM brass cap marked per the diagram on 2-1/2" pipe, 6 inches above ground, from which: 22" Ponderosa Pine bears N.34°W., 167.0 feet with visible scribing.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 5/8" x 24" rebar with 2" aluminum cap, bears West., 48.5 feet, stamped WSI/RM 48.5, 2535.

Reference monuments have an arrow pointing towards the corner. Appropriate signs have been attached to all bearing trees as required by this US Forest Service contract. 20° declination was used. Fieldwork was performed in May 2002.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Michael P. LeJeune

OREGON
JAN. 21, 1992
MICHAEL P. LE JEUNE
2535

11/06/02
EXPIRES 12/31/02

Prepared by: White Shield, Inc.
2515 W. Falls Ave.
Kennewick, WA 99336

Michael P. LeJeune,
Oregon PLS. 2535

Office ofCounty Surveyor....., County ofUmatilla.....,State of Oregon, I hereby certify that the within

instrument was filed in this office for record on theday of

David H. K...
(County Official)

RECEIVED BY
Umatilla County Surveyors
(Deputy) Date 11-02
Rec'd By XK
No. 02-273-A