

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established in 1882 by Herman D. Gradon, US Deputy Surveyor, under Contract Number 452. The Surveyor General's records state:

Set a basalt stone 17x6x5 ins 11 ins in the ground for 1/4 sec cor marked 1/4 on N-face from which:

A pine 5 ins diam. bears N.80°W. 46 lks dist. marked 1/4 S.B.T.

A pine 18 ins diam bears S.20°E. 73 lks dist. marked 1/4 S.B.T.


1982, A. Joseph Garrison, Cadastral Surveyor under Bureau of Land Management Group No. 1000. The field notes state:

The 1/4 sec. cor. of secs. 9 and 16, monumented with the original basalt stone, 17 x 6 x 5 ins., loosely set 3 ins. in the ground, mkd. 1/4 on the N. face from which the original bearing trees:

A ponderosa pine, 27 ins. diam., bears S.24°E., 70 lks. dist., with healed blaze.

A ponderosa pine, 17 ins. diam., bears N.70°W., 46 lks. dist., with healed blaze.

At the corner point, set aluminum post, 28 ins. long, 2-1/2 ins. diam., 24 ins. in the ground, in a mound of stone, 2 ft. base, to top, with aluminum cap. Deposit corner stone alongside the aluminum post.



Description of corner evidence found:

Found 3-1/4" BLM aluminum cap marked per the diagram on 2-1/2" pipe in large rock mound, from which;

23" Ponderosa Pine bears N.69°W., 29.4 feet with a healed face.

34" Ponderosa Pine bears S.24°E., 45.5 feet with a healed face

Description of monument and accessories | established to perpetuate the original location of this corner:

Set 5/8" x 24" rebar with 1-1/2" aluminum cap, bears East, 48.2 feet, stamped WSI/RM 48.2, 2535.

Set 5/8" x 24" rebar with 1-1/2" aluminum cap, bears North, 46.5 feet, stamped WSI/RM 46.5, 2535.

Reference monuments have an arrow pointing towards the corner. Appropriate signs have been attached to all bearing trees as required by this US Forest Service contract. 20° declination was used. Fieldwork was performed in May 2002.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Michael P. LeJeune

OREGON 11/06/02
JAN. 21. 1992
MICHAEL P. LE JEUNE
2535

EXPIRES 12/31/02

Prepared by: White Shield, Inc.
2515 W. Falls Ave.
Kennewick, WA 99336

Michael P. LeJeune,
Oregon PLS. 2535

Office ofCounty Surveyor....., County ofUmatilla.....,State of Oregon, I hereby certify that the within

instrument was filed in this office for record on theday of

David H. ...
.....
(County Official)

RECEIVED BY

Umatilla County Surveyor

(Deputy) Date 11-02

Rec'd By KK

No. 02-273-B