

Index
 File No. N-05
 T IN R. 36E
 Merid. WILLAHETTE

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or Survey No. _____
 Cor. No. _____

R.D. WALLA-WALLA County WATILLA
 N.F. WATILLA State OREGON

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

3 1/4" BRASS CAP ON 2 1/2" IRON PIPE RISING 4" IN MOUND OF STONES

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

14" PONDEROSA PINE BEARS N 29 1/4° E ~ 64 LKS - 42 1/2 FT BL. & SCRIBED TIN R36E S17BT
13 3/4" PONDEROSA PINE BEARS S 77 1/2° E ~ 30 LKS - 19 1/2 FT BLAZED & SCRIBED TIN R36E S20BT
13 3/4" PONDEROSA PINE BEARS S 1 1/2° W ~ 70 LKS - 46 1/2 FT BLAZED & SCRIBED TIN R36E S19BT
8 1/2" PONDEROSA PINE BEARS N 1 1/4° W ~ 78 LKS - 51 1/2 FT BLAZED & SCRIBED TIN R36E S18BT

PHOTO IDENTIFICATION DATA

Photo No. _____
 Filed At. _____
 Object Ident. _____
 Ident. By _____
Signature

PLANE COORDINATE POSITION DATA

State _____ Zone _____
 X _____
 Y _____
 Estab. By _____
Agency

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

CORNER IS 400 FT EAST OF RIDGETOP ROAD 3030-050 ON EASTERLY SLOPE AT WEST EDGE OF TIMBER

Signature _____ Title _____ Division _____ Headquarters _____ Date _____
PLS 1848 11-19-84 7100-52-(3/68)

CORNER RECORD (PERPETUATION)

MONUMENT : DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

SET STEEL FENCE POSTS WITH 54-2 & 54-4 SIGNS ATTACHED
3 FT SOUTH OF CORNER MONUMENT

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

ATTACHED 54-4 SIGNS ON SIDE OF TREES AWAY FROM CORNER,
PAINTED BLAZES & RED BANDS AROUND TREES.

Work Done By: BA. SUTTON Title SURVEYOR Date 11-19-85 State Registration No. PLS 1848
or Agency

Certified Cor. Record Prepared ? Yes No Filed At: _____ Date _____

REMARKS

Index File No.

N-05

T. 1N

R. 36E


M. KILLAMETTE Tract or Surv. No.

Cor. 18/17
19/20

LAND CORNER RECORD

1. T T1N RR36E No. N5 Cor. Sec Mer. Will State Oregon (Rectangular) N. F. Umatilla Dist. Pend 5

2. Corner Status



7. Photo Identification

Photo No. _____
Ident. By: _____

8. Plane Coordinate Position Data

State _____ Zone _____
X _____
Y _____
Estab. By _____
Field Book No. _____
Where Filed _____

9. Evaluation

Authentic _____
Needs Verif. _____ Monument _____
Re-estab. _____ Survey X
Land Status on Forest Boundary

3. Original Description _____ Vol. 281 Page 502 Where Recorded BLM Portland

4. Description of Corners: Set a post 4' long, 4" sq., 24" in ground for cor. to Sec. 17, 18, 19, 20, marked T1N S17 on NE, R36E S20 on SE, S19 on SW & S18 on NW face with 3 notches on S & 5 notches on E edges, from which a pine 6" dia bears N45°E 11 lks marked T1N R36E S17 BT, a pine 28" dia bears S60°E 25 lks marked T1N R36E S20 BT a fir 4" dia bears S25° W 22 lks marked T1N R36E S19 BT a fir 7" dia bears N35°W 89 lks marked

5. Investigation Notes: T1N R36E S18 BT

The corner was searched for by following a down fence line from the Horseshoe Ridge Rd No. N-208 in an easterly direction for as much as a 1/4 mile, traversing back & forth across the fence line & its projection

No evidence of the corner was found.

There was evidence of an old fire having been in the area which may have destroyed the bearing trees.

6. Signed R. C. Holmes Title Engineering Asst Date 4-25-62

PERPETUATION RECORD

10. Monument:

11. Accessories

Field Book _____ Page _____

12. Set By _____ Title _____

13. Recorded By _____ Volume _____ Page _____

(Agency)

License _____ Agency _____ Date _____

(Date) _____ (City) _____ (County) _____ (State) _____

14. Remarks:

N-5