

USDA-FOREST SERVICE

Index

CORNER RECORD (SEARCH)

Tract or

Cor.

File No. Z-23

(Ref. FSM 7151.4)

Survey No. _____

No. _____

T 1N R. 36E

R.D. WALLA WALLA

County UMATILLA

Merid. WILLAMETTE


N.F. UMATILLA

State OREGON

CORNER DIAGRAM

DESCRIBE CORNER MONUMENT FOUND

Found no evidence of the original corner.



DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

Found no evidence of the original accessories.

PHOTO IDENTIFICATION DATA

Photo No. 12 616140A 787-57

Filed At. Ranger Office

Object Ident. 30" White Fir

Ident. By D.I. Griffith

Signature

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Corner falls on timbered South slope approximately 50 feet South of a private road, approximately 300 feet East of a junction in the road.

PLANE COORDINATE POSITION DATA

State _____ Zone _____

X _____

Y _____

Estab. By _____

Agency

Signature

Title Surveyor

Division _____

Headquarters _____

Date

FS-7100-52 (3/68)

8-24-89

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set a 2½"x30" aluminum pipe with aluminum cap marked as shown:
Pipe is set 28 inches in the ground.

T1N R36E
S C
¼ S 36

Raised mound of stone around monument, 2 ft. base to top of cap.

T1S
1989
OPLS 644

9

ACCESSORIES : DESCRIBE NEW BT's WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

New BTs:

A 10 inch diameter Douglas Fir bears N30°E, 20.26 feet marked ¼ S36 SC BT
A 20 inch diameter White Fir bears N45°W, 19.27 feet marked X BT

Painted a 6 inch red band around all BTs and attached 54-3 and 54-9 signs.

Set steel fence post approximately 5 feet East with 54-9 ~~signs~~ signs attached

10

Work Done By D.I. Griffith Title Surveyor Date 8-15-89 State Registration No. or Agency OPLS 644

Certified Cor. Record Prepared? Yes No Filed At: Umatilla Co. Surveyor's Office Date 9-89

11

REMARKS

Witnesses: Rick Robinson and Jeff Petersen.

Index File No. Z-23

T. 1N

R. 36E

W.M.

Tract or Surv. No.

Cor.

12

13