

OREGON CORNER RESTORATION FORM

Section 30 Township 1 N Range 37 E.

County Umatilla Date Sept., 1993

CORNER DESIGNATION

1/4 corner common to sections 30/29
corner index: T-5

<input type="checkbox"/>	Condition Report Only
<input type="checkbox"/>	Not Found
<input type="checkbox"/>	Renewed
<input type="checkbox"/>	Unrecorded
<input checked="" type="checkbox"/>	Surveyed In
<input type="checkbox"/>	Referenced Out

Previous Renewals/Surveys, etc.

1882 Herman Gradon, set a basalt stone 15"x9"x6", 10" in the ground, marked with a 1/4 on the west face with a mound of stone raised alongside. No bearing trees were available.

Monument(s) & Accessories Found: (Condition and Source)

No evidence was found. Corner positions searched included the single proportion position and record distances from each section corner.

Monument Detail

Sketch



Monument Set (Procedures and Description)

At a single proportion position I set a 3-1/4" aluminum cap on a 2-1/2"x 30" aluminum pipe, 24" in the ground with a rock cairn, with a land survey monument sign attached to a steel post nearby.

New Accessories

21" douglas bears S.30-1/2°W., 10.3 feet scribed 1/4S30BT.
 10" douglas fir bears S.48°E., 21.5 feet scribed 1/4S29BT.
 1-1/2" aluminum cap (PLS 2535) on a 5/8"x 24"rebar bears N.42-1/2°E., 14.1 ft, cap is stamped 14.1 RM with an arrow pointing toward the corner.
 1-1/2" aluminum cap (PLS 2535) on a 5/8"x 24"rebar bears N.20-1/2°W., 12.7 ft, cap is stamped 12.7 RM with an arrow pointing toward the corner.

I painted a 6" red band around all bearing trees and attached a bearing tree sign on the front with a land survey monument sign on the back. On the new bearing trees I attached a brass washer "PLS 2535" in the BT portion of the blaze.

Location & Comments

RECEIVED BY
 Umatilla County Surveyor
 Date 12-93
 Rec'd by KP
 No. 93-93-B

Compass Declination 18° east
 Firm/Agency: White Shield, Inc
 Address: P.O. Box 477,
Grandview, WA 98930
 Party Chief: Dennis Hartmans
 Notes field bk. 3, pg. 9
 Witness Wes Cochran

Surveyor's Seal

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

Michael P. LeJeune

OREGON 11/4/93
 JAN. 21, 1992
 MICHAEL P. LE JEUNE
 2535