


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

E - 1  
DIAGRAM

**History of original corner establishment:**

The original corner was established by George S. Pershin, deputy, (compassman) on September 11, 1871, under joint GLO contract No. 154, as follows:

Set a stone, 18" x 10" x 7", on northwest side of spur for corner to sections 1, 6, 7 and 12.



**Original corner evidence recovered:**

Found the original corner stone loosely set in a mound of stones. The corner stone is 19" x 11" x 7" and is plainly marked with one notch on one (north) edge.

**Monument and accessories established to perpetuate the original position of this corner:**

In place of the original corner stone, I set a 1" x 30" flared, galvanized iron pipe 28" into the ground. A 2 1/2" brass cap attached to the top of the iron pipe is marked as shown in the diagram above. I bury the corner stone along the south side of the pipe and build a mound of stones around the pipe, from which:

- A 5/8" x 24" iron rod set 23" into the ground, with a 3/4" brass washer, marked "PLS 1636 S6", attached at ground level, bears N57° E, 49.2 feet.
- A 5/8" x 36" iron rod set 35" into the ground, with a 3/4" brass washer, marked "PLS 1636 S7", attached at ground level, bears S54° 30' E, 69.9 feet.
- A 5/8" x 36" iron rod set 35" into the ground, with a 3/4" brass washer, marked "PLS 1636 12", attached at ground level, bears S22° W, 81.4 feet.
- A 5/8" x 24" iron rod set 22" into the ground, with a 3/4" brass washer, marked "PLS 1636 S1", attached at ground level, bears N69° W, 42.0 feet.

I hereby certify the above corner point was perpetuated as hereon described on October 24, 2002. Magnetic declination set in compass: 18° E. NAD '83 UTM Zone 11 position: 5040966N 332404E (plus or minus two meters).

5040966N  
332404E

*Dennis L. Gaylord*

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

OREGON  
JULY 14, 1978  
DENNIS L. GAYLORD  
1636

Renews June 30, 2003

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on:

RECEIVED BY  
Umatilla County Surveyor  
Date 11-02  
Rec'd By KK  
No. 02-271-R