

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

G - 1
DIAGRAM

History of original corner establishment:

The original corner was established on September 11, 1871, by George S. Pershin, deputy (compassman) under joint GLO contract No. 154, as follows:

Set stone, 24" x 8" x 5", on northeast hillside for 1/4 section corner.

T1S
1/4
S12|S7
R29E | R30E
PLS 1636
2002

Original corner evidence recovered:

Found original corner stone solidly set protruding 6" from the ground. The corner stone is 24" x 10" x 6" and is plainly marked "1/4" on the west face.

Monument and accessories established to perpetuate the original position of this corner:

In place of the original corner stone, I set a 1" x 30" galvanized iron pipe 28" into the ground. A 2 1/2" brass cap attached to the iron pipe is marked as shown in the diagram above. I bury the original corner stone along the southwest side of the pipe and build a mound of stones around the pipe, from which:

- A 5/8" x 36" iron rod, set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 NE", attached at ground level, bears N55° 30' E, 49.8 feet.
 - A 5/8" x 36" iron rod, set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 SE", attached at ground level, bears S26° 30' E, 63.4 feet.
 - A 5/8" x 36" iron rod, set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 SW", attached at ground level, bears S62° W, 70.8 feet.
 - A 5/8" x 36" iron rod, set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 NW", attached at ground level, bears N47° W, 102.5 feet.
- A fence corner with standing wire fences projecting northeast, northwest and southwest, and the remains of an ancient fence projecting southeast, bears N12° W, about 150 feet.

I hereby certify the above corner point was perpetuated as hereon described on November 7, 2002. Magnetic declination set in compass: 16°E. (The range line is visible to the north)
NAD '83 UTM Zone 11 position: 5040157N 332368E (plus or minus two meters)

Dennis L. Gaylord

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 14, 1978
DENNIS L. GAYLORD
1636

Renews June 30, 2003

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on:

RECEIVED BY
Umatilla County Surveyor
Date 11-02
Rec'd By KE
No. 02-272-R